NOTICE OF SPECIAL MEETING OF THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, TEXAS

Notice is hereby given that, beginning at 5:00 p.m. on Tuesday, November 3, 2026, and continuing from day to day thereafter if necessary, the City Council of the City of Harker Heights, Texas, will hold a Special meeting in the Kitty Young Council Chamber at 305 Miller's Crossing, Harker Heights, Texas 76548. The subjects to be discussed are listed in the following agenda:

MEETING AGENDA

I. **INVOCATION:**

II. **ROLL CALL:**

III. **PLEDGE OF ALLEGIANCE:**

I Pledge Allegiance to the Flag of the United States of America and to the Republic for which it stands, one nation under God, indivisible, with liberty and justice for all.

Honor the Texas Flag. I pledge allegiance to thee Texas; one State under God, one and indivisible.

IV. **MAYORAL PROCLAMATIONS AND PRESENTATIONS:**

1. Proclamation declaring November 2nd through 6th, 2026, as "Municipal Court Week".
Proclamation

V. **PRESENTATIONS BY CITIZENS:**

Citizens who desire to address the Council on any matter may do so during this item. Please understand that while the Council appreciates hearing your comments, State law (Texas Gov't Code §551.042) prohibits them from: (1) engaging in discussion other than providing a statement of specific factual information or reciting existing City policy, and (2) taking action other than directing Staff to place the matter on a future agenda. Please state your name and the city of residence for the record and limit your comments to three minutes.

VI. **RECESS INTO EXECUTIVE SESSION:**

1. Pursuant to the following designated section of the Texas Government Code, Annotated, Chapter 551, the Council may convene into executive session to discuss the following:

A) Pursuant to §551.074 of the Texas Government Code - Deliberate the appointment of public officers to the Planning and Zoning Commission/Building Standards Commission.

B) Pursuant to §551.074 of the Texas Government Code - Deliberate the appointment of public officers to the Zoning Board of Adjustment.

C) Pursuant to §551.072 of the Texas Government Code - Discussion regarding the purchase, exchange, lease, or value of real property in the City of Harker Heights which deliberation in an open meeting would have a detrimental effect on the City's position in negotiations with a third person.

VII. **RECONVENE INTO OPEN SESSION:**

VIII. **REGULAR BUSINESS:**

1. Discussion and possible action regarding the appointment of members to the Planning & Zoning Commission (P&Z), Building Standards Commission (BSC), and Zoning Board of Adjustments (ZBA). (City Secretary)

   Staff Report - Pdf

2. Discussion and possible action regarding the appointment of members to the Animal Advisory Committee; Harker Heights Arts Commission; Economic Development Advisory Committee; Library Board; Parks & Recreation/Tree Advisory/Keep Harker Heights Beautiful Board; Public Safety Commission; and Capital Improvement Advisory Committee. (City Secretary)

   Staff Report - Pdf

3. Discuss and consider approving a Preliminary Plat referred to as The Sanctuary at Harker Heights Preliminary Plat, being 68.90 acres of land out of the James M. Cross Survey, Abstract No. 179 and the W.H. Webb Survey, Abstract No. 1016, Bell County, Texas, and being all of a called 20.00 acre tract of land as described by a deed to C.A. DOOSE & COMPANY, a Texas Corporation, recorded in Document No. 2022017402, Real Property Records in Bell County, Texas, and being all of a called 48.91 acre tract of land as described by a deed to said owner recorded in Document No. 2021051936, of said Property Records. (Planning Administrator)

   P26-14 Staff Report - Pdf

4. Discuss and consider approving a Final Plat referred to as Ranger Top Addition Final Plat, a 1.003 ACRE, situated in the Elizabeth Dawson Survey, Abstract 258, Bell County, Texas, and being all of that certain tract described as 1.0 acre in a General Warranty Deed with Vendor's Lien, to Ranger Top, LLC., recorded in Document No. 2022004499, Official Public Records of Real Property, Bell County, Texas. (Planning Administrator)

   Staff Report - Pdf

5. Discussion and possible action regarding approval of a Resolution of the City Council of the City of Harker Heights, Texas, authorizing the submission of an application for the 2027-2028 TxCDBG Community Development Fund competition. (Resolution #2026-36; Project Manager)

   Staff Report - Pdf

6. Discussion and possible action regarding approval of a Signatory Resolution authorizing signatories for the 2027-2028 application and future grants administered through Texas Department of Agriculture TDA-GO grants online portal. (Resolution #2026-37; Project Manager)

   Staff Report - Pdf

7. Receive and discuss the City Manager's Report.

IX. **MATTERS FOR DISCUSSION:**

1. Receive and discuss a presentation regarding the City's Solid Waste Collection and Disposal Services. (City Manager)

   Staff Report - Pdf

X. **ITEMS FROM COUNCIL AND ANNOUNCEMENTS:**

1. Councilmember closing statements.

2. Updates and comments from the Mayor.

XI. **ADJOURNMENT:**

I hereby certify that the above notice of meeting was posted on the bulletin board of City Hall, City of Harker Heights, Texas, a place readily accessible to the general public at all times, on the 27th of October 2026, by 5:00 p.m. and remained posted for at least three continuous business days preceding the scheduled date of said meeting.

Julie Helsham
City Secretary

This facility is wheelchair accessible and accessible parking spaces are available. Requests for accommodations or interpretive services must be made 48 hours prior to this meeting. Please contact the City Secretary's office at 254-953-5600, or FAX 254-953-5614, or email jhelsham@harkerheights.gov for further information. Pursuant to Chapter 551 of the Government Code the City Council reserves the right to go into Closed Meeting on any item listed above if deemed necessary. Note: On occasion the City Council may consider agenda items out of order.

Proclamation
Municipal Court Week

Whereas, the Municipal Court of Harker Heights, a time honored and vital part of the City of Harker Heights, has existed since 1960; and

Whereas more people, citizens and non-citizens alike, come in personal contact with municipal courts than all other Texas courts combined, and public impression of the entire Texas judicial system is largely dependent upon the public's experience in municipal court; and

Whereas, Municipal Judges and Court personnel continually strive to improve the administration of justice and have pledged to be ever mindful of their neutrality and impartiality, rendering equal service to all, and conform to the standards set by the Canons of Judicial Conduct; and

Whereas, it is most appropriate that we recognize the accomplishments of the 950 Texas Municipal Courts, and salute their critical role in preserving public safety, protecting the quality of life in Texas communities, and deterring future criminal behavior.

Now therefore, I, Michael Blomquist, Mayor of the City of Harker Heights, do hereby proclaim the week of November 2nd through November 6th, 2026, as

"Municipal Court Week"

and further extend appreciation to all Harker Heights Municipal Court personnel for the vital services they perform and their exemplary dedication to our community.

In Witness Thereof, I have signed this proclamation and have affixed the Seal of the City of Harker Heights, Texas, this 3rd day of November 2026.

_____

Michael D. Blomquist
Mayor

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

DISCUSSION AND POSSIBLE ACTION REGARDING THE APPOINTMENT OF MEMBERS TO THE PLANNING & ZONING COMMISSION (P&Z), BUILDING STANDARDS COMMISSION (BSC), AND ZONING BOARD OF ADJUSTMENTS (ZBA). (CITY SECRETARY)

EXPLANATION:

Consider appointments to the following Boards/Commissions/Committees:
A. Planning & Zoning Commission/Building Standards Commission
B. Zoning Board of Adjustments

A. PLANNING & ZONING COMMISSION/BUILDING STANDARDS COMMISSION:

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Regular Member		3 years
Regular Member		3 years
Alternate #1		3 years
Alternate #2		3 years
Alternate #3 Unexpired Term		2 years
Alternate #4 Unexpired Term		2 years

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Planning & Zoning Commission/Building Standards Commission to take effect on January 1, 2027:
   _____.
2. Any action desired by the City Council.

B. ZONING BOARD OF ADJUSTMENTS:

Position	Name of Reappointed Member or New Member	Term
Regular Member		2 years
Regular Member		2 years
Regular Member Unexpired Term		1 year
Alternate #1		2 years
Alternate #2 Unexpired Term		1 year
Alternate #3		2 years

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Zoning Board of Adjustments to take effect January 1, 2027: _____.
2. Any action desired by the City Council.

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

DISCUSSION AND POSSIBLE ACTION REGARDING THE APPOINTMENT OF MEMBERS TO THE ANIMAL ADVISORY COMMITTEE; HARKER HEIGHTS ARTS COMMISSION; ECONOMIC DEVELOPMENT ADVISORY COMMITTEE; LIBRARY BOARD; PARKS & RECREATION/TREE ADVISORY/KEEP HARKER HEIGHTS BEAUTIFUL BOARD; PUBLIC SAFETY COMMISSION; AND CAPITAL IMPROVEMENT ADVISORY COMMITTEE (CITY SECRETARY)

EXPLANATION:

Consider appointments to the following Boards/Commissions/Committees:
A. Animal Advisory Committee
B. Arts Commission
C. Economic Development Advisory Committee
D. Library Board
E. Parks & Recreation/Tree Advisory/Keep Harker Heights Beautiful Board
F. Public Safety Commission
G. Capital Improvement Advisory Committee

A. ANIMAL ADVISORY COMMITTEE

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Regular Member (City Rep Position)		3 years
Alternate #1		1 year
Alternate #2		1 year

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Animal Advisory Committee to take effect on January 1, 2027: _____.
2. Any action desired by the City Council.

B. ARTS COMMISSION:

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Regular Member Unexpired Term (Chamber Member Position)		2 years
Alternate #1		1 year
Alternate #2		1 year

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following member of the Arts Commission to take effect on January 1, 2027: _____.
2. Any action desired by the City Council.

C. ECONOMIC DEVELOPMENT ADVISORY COMMITTEE:

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Regular Member		3 years

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Economic Development Advisory Committee to take effect January 1, 2027: _____.
2. Any action desired by the City Council.

D. LIBRARY BOARD:

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Alternate #1		1 year
Alternate #2		1 year

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Library Board to take effect on January 1, 2027: _____.
2. Any action desired by the City Council.

E. PARKS & RECREATION/TREE ADVISORY/KEEP HARKER HEIGHTS BEAUTIFUL BOARD:

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Regular Member		3 years
Regular Member		3 years
Alternate #1		1 year
Alternate #2		1 year

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Parks & Recreation/Tree Advisory/Keep Harker Heights Beautiful Board to take effect January 1, 2027: _____.
2. Any action desired by the City Council.

F. PUBLIC SAFETY COMMISSION:

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years
Regular Member		3 years
Alternate #1		1 year
Alternate #2		1 year

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following members of the Public Safety Commission to take effect on January 1, 2027: _____.
2. Any action desired by the City Council.

G. CAPITAL IMPROVEMENT ADVISORY COMMITTEE (CIAC):

Position	Name of Reappointed Member or New Member	Term
Regular Member		3 years

ACTION BY THE CITY COUNCIL:

1. Motion to appoint the following member of the Capital Improvement Advisory Committee to take effect on January 1, 2027: _____.
2. Any action desired by the City Council.

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

DISCUSS AND CONSIDER APPROVING A PRELIMINARY PLAT REFERRED TO AS THE SANCTUARY AT HARKER HEIGHTS PRELIMINARY PLAT, BEING 68.90 ACRES OF LAND OUT OF THE JAMES M. CROSS SURVEY, ABSTRACT NO. 179 AND THE W.H. WEBB SURVEY, ABSTRACT NO. 1016, BELL COUNTY, TEXAS, AND BEING ALL OF A CALLED 20.00 ACRE TRACT OF LAND AS DESCRIBED BY A DEED TO C.A. DOOSE & COMPANY, A TEXAS CORPORATION, RECORDED IN DOCUMENT NO. 2022017402, REAL PROPERTY RECORDS IN BELL COUNTY, TEXAS, AND BEING ALL OF A CALLED 48.91 ACRE TRACT OF LAND AS DESCRIBED BY A DEED TO SAID OWNER RECORDED IN DOCUMENT NO. 2021051936, OF SAID PROPERTY RECORDS. (PLANNING ADMINISTRATOR)

EXPLANATION:

REFERENCES:
Case #P26-14
MGO #2026-216

The applicant submitted an application for a Preliminary Plat referred to as The Sanctuary at Harker Heights Preliminary Plat for a 68.90 acre tract of land located along the western portion of Big Valley Lane. The purpose of this Preliminary Plat is to 106 residential lots.

The proposed subdivision is consistent with the existing zoning of R-1 (One-Family Dwelling District).

A Preliminary Plat application was submitted on September 1, 2026 and was forwarded to the Planning & Zoning Commission on September 30, 2026 for consideration. The Planning & Zoning Commission voted (7-0) to recommend disapproval of the preliminary plat. The application was withdrawn by the applicant on October 1, 2026.

The current Preliminary Plat application was submitted on October 1, 2026. Staff reviewed the submitted plat documents and provided comments addressing safety and compliance with applicable development regulations in the City of Harker Heights Code of Ordinances. Comments were provided to the applicant on October 19, 2026.

As of October 22, 2026, comments remain outstanding. See the attachment titled:

- “P26-14_CombinedComments_The Sanctuary at Harker Heights (MGO 2026-216) – 10-19-26”

Any additional submittals and corresponding comments will be provided to the City Council at the time of the meeting.

Particular attention during the review of Preliminary plats is given to the arrangement, location, and width of streets and access easements; their relationship to the topography; utility infrastructure including water, wastewater, and drainage; the coordination with future development of adjacent properties; and compliance with applicable city ordinances, policies, and plans.

RECOMMENDATION:

The Planning & Zoning Commission will meet on October 28, 2026 to consider approval of this plat. At the time this staff report was created, the Planning & Zoning Commission had not held its meeting. Staff will provide the Planning & Zoning Commission's recommendation and staff's recommendation at the City Council meeting.

ACTION BY THE CITY COUNCIL:

1. Motion to **approve** of a request for a Preliminary Plat referred to as The Sanctuary at Harker Heights Preliminary Plat, as read in the caption by the Mayor, based on the **discussed** recommendations and findings.
2. Motion to **approve with condition** of a request for a Preliminary Plat referred to as The Sanctuary at Harker Heights Preliminary Plat, as read in the caption by the Mayor, based on the **discussed** recommendation and findings, **with the following conditions:**
    a. All outstanding comments shall be addressed as directed by staff prior to the release of infrastructure permits and the submission of the Final Plat.
3. Motion to **disapprove with explanation** of a request for a Preliminary Plat referred to as The Sanctuary at Harker Heights Preliminary Plat, as read in the caption by the Mayor, based on the **discussed** recommendations and findings**with the following explanation: Applicant has not met the requirements of §154: SUBDIVISIONS**
4. Any other action desired.

ATTACHMENTS:

P26-14_Preliminary Plat Application
P26-14_Preliminary Plat Checklist
P26-14_Location
P26-14_Lot Lines
P26-14_Dedication
P26-14_Field Notes
P26-14_Preliminary Plat
P26-14_CombinedComments_The Sanctuary at Harker Heights (MGO 2026-216) - 10-19-26

Preliminary Plat Application

City of Harker Heights
Planning & Development
305 Millers Crossing
Harker Heights, TX 76548
Phone: (254) 953-5600
Email:
planning@harkerheights.gov

*** Requirements - APPLICATION MUST BE FULLY COMPLETED OR WILL NOT BE ACCEPTED***

This application must be completed and returned to the Planning and Development Department of the City of Harker Heights, Texas along with the following:

1. **Pre-Application Meeting with Staff to ensure applicability**
2. **Payment, refer to most recently approved fee schedule**
3. **Signed Original Field Notes and Dedication Pages**
4. **Paper Plan Submissions: Ten (10) Copies of the Plat and Seven (7) Copies of Preliminary Engineering Drawings**
5. **Electronic Submission of all documents for review delivered to Planning Administrative Assistant**

Property Information:

Plat Name: The Sanctuary At Harker Heights **Date Submitted:** 10/01/2026

Existing Lot Count: 0 **Proposed Lot Count:** 106 **Proposed Units:** 106 **Acreage:** 68.90

Existing Land Use: Ag / Undeveloped **Proposed Land Use:** Single-Family Residential

Site Address or General Location: SE corner of FM 2410 & Big Valley Rd

Public Infrastructure Proposed with Subdivision: ☑ Water ☑ Wastewater ☑ Streets (including Private) ☑ Stormwater

Owner Information & Authorization:

Property Owner: Doose, C A & Company
Address: 800 Kennedy Ct, Belton, Texas 78513
Phone: (254) 290-3148 E-Mail: craig@flintrockbuilders.com

Developer: Flintrock Builders
Address: 800 Kennedy Ct, Belton, Texas 78513
Phone: (254) 290-3148 E-Mail: craig@flintrockbuilders.com

Engineer/Surveyor: Republic Engineering
Address: 6305 Pat Cole, Temple, Texas 76502
Phone: (512) 665-8910 E-Mail: jtheriot@RepublicEDS.com

CHECK ONE OF THE FOLLOWING:

☐ I will represent the application myself.

☑ I hereby designate Republic Engineering (name of project representative) to act in the capacity as my agent for submittal, processing, representation, and/or presentation of this development application.

The property owner and/or their authorized representative must be present at all Planning and Zoning Commission Meetings and City Council Meetings at which their plan or plat is on the agenda for discussion or action. Failure of the developer or their authorized representative to appear during a meeting may be deemed a withdrawal of the plat or plan.

Christopher A. Doose, IV
Printed Name of Owner

Signature of Owner

JON MARK ENTERKIN
NOTARY PUBLIC STATE OF TEXAS
Notary Public, State of Texas
Comm. Expires 12-04-2027
Notary ID 134665753

SWORN AND SUBSCRIBED BEFORE ME ON THIS 26 *DAY OF* August, 2026.

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS *MY COMMISSION EXPIRES:* 12-4-27

STAFF ONLY -- DO NOT FILL OUT

Date Submitted: _____ Received By: _____ Receipt #: _____

For Office Use Only

Project # _____

Preliminary Plat/ Revised Preliminary Plat Checklist

The following is a partial listing of requirements for Preliminary Plat and Revised Preliminary Plat applications as found in the City of Harker Heights' Code of Ordinances and policies. A completed checklist must be submitted with each application. All applications are required to be submitted via the City's online portal at https://www.mygovernmentonline.org/. Applications are only accepted on the dates indicated in the adopted annual intake calendar (https://harkerheights.gov/index.php/boards-and-commissions/planning-and-zoning/p-z-commission). Applicants shall indicate compliance with standards by checking the box adjacent to the standard. Failure to comply with standards could result in rejection of application, delay of preliminary plat/preliminary replat approval, and/or disapproval. This checklist is in accordance with §154.20(A)(1) and §154.21 of the City's Code of Ordinances.

Section 1 – General Provisions *(check if provided; indicate NA if not applicable)*

Please clarify the status of this Preliminary Plat / Revised Preliminary Plat (Plat) submittal:

☑ **1.1** A pre-application meeting with the City's Development Review Committee has been held for this Plat area. **(§154.20(A)(1)(a))**

Date of Meeting: several of the past year.

☑ **1.2** A Concept Plan was previously approved /conditionally approved for this Plat area. **(§154.20(A)(2))**

Date of Approval: 11/14/2023; Case Number: CP-23-03.

N/A ☐ **1.3** Concurrent filing of this Plat with a Concept Plan was approved in writing by the Planning & Development Director. **(§154.20(A)(2)(e))**

Date of Approval: _____.

N/A ☐ **1.4** This is a replat of a previously approved Preliminary Plat. **(§154.21(B))**

Name of original Preliminary Plat: _____.

Date original Preliminary Plat was approved: _____.

Change in the number of Lots from _____ to _____.

Section 1 – General Provisions cont. *(check if provided; indicate NA if not applicable)*

Proposed Change in infrastructure was deemed in writing a minor amendment by the Public Works Director. **(§154.21(B)(3))**

Date of Approval: _____.

☑ **1.5** Total area for this Plat is: 68.90 (acres); _____ (square feet).

☑ **1.6** Current Zoning District(s) for this Plat area is:

R-1.

☑ **1.7** Number of Lots/Tracts/Remainders Per respective Zoning District in this Plat area is:

106 Lots, 3 Tracts, 5 Blocks.

Section 2 – Legal *(check if provided; indicate NA if not applicable)*

☑ **2.1** Provide a completed application form and fees. **(§154.20(B)(1-2))**

☑ **2.2** Provide proof of ownership for the Plat area. **(§154.20(A))**

- Copy of deed
- For businesses, non-profits, etc. provide signed documentation authorizing applicant to sign on behalf of the entity. **(§154.20(A)(6))**

☑ **2.3** Provide a copy of recorded documentation for existing easements.

Section 3 – General Plat Standards *(check if provided; indicate NA if not applicable)*

☑ **3.1** Illustrate and label all phases of development for land under the same ownership. **(§154.21(A))**

☑ **3.2** Provide two hard copies of the Plat and engineering drawings. **(§154.20(B)(3)(a) and §154.21 (C))**

- Hard copies are legible such that they can be clearly reproduced.
- Line types and weights are clearly identifiable in black and white and upon reproduction.
- Abandonments are indicated with shading or hatching and are labeled “To be abandoned by this plat.”.
- ROW dedication is indicated with a unique shading or hatching and are labeled.

☑ **3.3** Plat is sealed by a Texas Licensed Professional Engineer or Texas Registered Professional Land surveyor. **(§154.21(C)(1))**

☑ **3.4** Sheet sizes shall be a 22” x 34” black and white drawing in landscape view at a scale of 1-inch = 100 feet. **(§154.21(C)(1))**

☑ **3.5** If submitting three or more sheets, provide a cover sheet with table of contents and a vicinity map that clearly shows the project’s location. **(§154.21(C)(1)(a))**

- The vicinity map shall be at a scale such that it is easy to determine what part of the city the project is located (major road name(s)).

Section 3 – General Plat Standards cont. *(check if provided; indicate NA if not applicable)*

☑ **3.6** Title block on each page includes: the proposed subdivision name, phase(s), block numbers, lot numbers, current legal description, acreage, name/address of property owner, name/address of surveyor, name/address of engineer, date of survey, date of preparation, page content title. **(§154.21(C)(1)(b) and §154.21(C)(1)(f))**

☑ **3.7** Index Sheet at 1-inch = 100 feet is provided if applicable. **(§154.21(C)(1)(c))**

N/A ☐ **3.8** Phasing Plan provided if applicable. **(§154.21(C)(1)(e))**

☑ **3.9** A north arrow is required on all sheets and should be oriented either upward or to the right. **(§154.21(C)(1)(n))**

- Orient the plan sheets such that north is toward the top or left-hand side of the sheet.

Section 4 – Plat Standards *(check if provided; indicate NA if not applicable)*

☑ **4.1** Provide legal description, existing boundary, lot lines and right-of-way lines of streets and easements with accurate dimensions, bearings, deflection angles, radii, and central angles of all curves. **(§154.21(C)(1)(d))**

- Label and illustrate all of the above items.
- Provide field notes for the Plat.
- Provide enough information for easements shall be such that they can be found in the field with the plans.
- Label types and dimensions of easements (proposed, existing, utility, drainage, access, etc.)

☑ **4.2** Lot lines shall have line dimensions clearly displayed within the lot along with the lot's respective lot number. Groups of lots that are considered within a block shall have the block number clearly displayed. **(§154.21(C)(1)(f))**

☑ **4.3** All right-of-way lines and easements shall be clearly displayed on the plat. The plat shall clearly display the location, size and purpose of all existing and proposed easements on or adjoining the property. **(§154.21(C)(1)(g))**

☑ **4.4** Location of existing and proposed streets, alleys, bikeways, and sidewalks on or adjoining the site. Such information shall include name, right-of-way widths, type and width of surfacing. All private streets shall be clearly labeled. **(§154.21(C)(1)(h))**

☑ **4.5** Identify (illustrate and label) any areas reserved or dedicated for public use. **(§154.21(C)(1)(i))**

☑ **4.6** Identify (illustrate and label) easements and street stub-outs necessary to serve adjacent properties. **(§154.21(C)(1)(j))**

- Refer to adjacent recorded plats, any recorded easements, the City's plans, the City's Thoroughfare plan, the City's sidewalk plan, the City's Hike and Bike plan and all of the City's various utility Master Plans. **(§154.21(C)(2)(D)(2-3))**
- TXDOT required marginal access easement.
- Provide field notes and other documents for offsite easement and/or R.O.W. dedication.

☑ **4.7** Adjacent property information including present ownership, legal descriptions (recorded volume and page or subdivision Lot and Block) and property lines within 100 feet. **(§154.21(C)(1)(k))**

- This includes properties across the street from the plat area.

Section 4 – Plat Standards cont. *(check if provided; indicate NA if not applicable)*

- ☑ **4.8** Primary control points or descriptions and ties to such control points to which all dimensions, angles, bearings, and similar data shall be referred. **(§154.21(C)(1)(l))**
- ☑ **4.9** The plat shall be located with respect to a corner of the surveyor tract, or an original corner of the original survey of which it is a part. Temporary benchmarks and NGS datum shall be described on each sheet. **(§154.21(C)(1)(l))**
- ☑ **4.10** Scale, basis of bearing and benchmarks (datum) and description shall all be clearly displayed on the plat. **(§154.21(C)(1)(m))**

Section 5 – Engineering Drawing Standards *(check if provided; indicate NA if not applicable)*

- ☑ **5.1** Preliminary Engineering Drawings are sealed by a Texas Licensed Professional Engineer. **(§154.21(C)(2))**
- ☑ **5.2** Sheet sizes shall be a 22” x 34” black and white drawing in landscape view at a scale of 1-inch = 100 feet. **(§154.21(C)(2))**
- ☑ **5.3** Comply with the standards of design and requirements in the current edition of the North Central Texas Council of Governments’ Standard Specifications for Public Works Construction and the City of Harker Heights’ Code of Ordinances. **(§154.21(C)(2), and Title XV.)**
- ☑ **5.4** Title block on each page includes: the proposed subdivision name, phase(s), block numbers, lot numbers, current legal description, acreage, name/address of property owner, name/address of surveyor, name/address of engineer, date of survey, date of preparation, page content title. **(§154.21(C)(2)(a))**
- ☑ **5.5** All stationing should start from cardinal points of the compass and proceed in the direction of construction. **(§154.21(C)(1)(n))**
- ☑ **5.6** Designs conform with the City’s engineering standards and specifications, City Ordinances, City Standards, City’s plans, the City’s Thoroughfare plan, the City’s sidewalk plan, the City’s Hike and Bike plan and all of the City’s various utility Master Plans. **(§154.21(C)(2)(D)(2))**
    - Utilize standard engineering scales for the preliminary engineering drawings.
- ☑ **5.7** Provide a Water Layout Plan that includes rough locations and labeling of the following **(§154.21(C)(2)(b)):**
    - water service connections
    - pipe diameters
    - valve locations
    - fire hydrants
    - flush assemblies
- ☑ **5.8** Provide a Sewer Layout Plan that includes rough locations and labeling of the following **(§154.21(C)(2)(c)):**
    - sewer service connections
    - pipe diameters
    - cleanouts
    - manholes

Section 5 – Engineering Drawing Standards *(check if provided; indicate NA if not applicable)*


☑ **5.9** Provide a Street and Sidewalk Layout Plan that includes rough locations and labeling of the following **(§154.21(C)(2)(d)):**

- proposed street names
- roadway classification
- ROW width
- sidewalk width
- alley width (if applicable)
- access easements (passage, trash, etc.)
- fire lanes (if applicable)


☑ **5.10** Provide a Stormwater Drainage Layout Plan that includes rough locations and labeling of the following **(§154.21(C)(2)(e)):**

- Include elevation contours
- Pipes and inlets
- Channels and flumes
- Include FEMA special flood hazard area boundaries (if applicable), and FEMA base flood elevations (if applicable)
- Identify conceptual area for a detention basin (if applicable)
- Include drainage calculations for major drainage structures (if applicable)

P26-14 Location



P26-14 Lot Lines



DEDICATION

STATE OF TEXAS

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF BELL

That **C.A. DOOSE & COMPANY, LLC**, being the owner of the land shown on this plat designated as **THE SANCTUARY AT HARKER HEIGHTS**, an addition to the City of Harker Heights, Bell County, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, watercourses, drains, easements, and public places as shown hereon.

WITNESS the execution hereof, on this _____ day of _____, 20__ A.D.

_____
Craig Langford, Agent

STATE OF TEXAS
COUNTY OF BELL

This instrument was acknowledged before me on this _____ day of _____, 20__ A.D. by Craig Langford.

_____
NOTARY PUBLIC STATE OF TEXAS
My Commission Expires: _____

THE SANCTUARY AT HARKER HEIGHTS
68.90 ACRES
BELL COUNTY, TEXAS

BEING 68.90 acres of land out of the James M. Cross Survey, Abstract No. 179 and the W.H. Webb Survey, Abstract No. 1016, Bell County, Texas, and being all of a called 20.00 acre tract of land as described by a deed to C.A. DOOSE & COMPANY, a Texas Corporation, recorded in Document No. 2022017402, Real Property Records in Bell County, Texas, and being all of a called 48.91 acre tract of land as described by a dee to said owner recorded in Document No. 2021051936, of said Property Records, and being more particularly described by metes and bounds as follows:

BEGINNING at a capped iron rod found in the intersection of the south right-of-way line of F.M. Road 2410 and the west right-of-way line of Big Valley Lane, for the northeast corner of said 20.00 acre tract, for the most northeasterly corner of this tract;

THENCE S 16°57'12" W, 1911.67 feet, with the east boundary line of said 20.00 acre tract and with the west right-of-way line of said Big Valley Lane, to a ½ inch iron rod found for the southeast corner of said 20.00 acre tract and for the southwest corner of said Big Valley Lane and being in the north boundary line of said 48.91 acre tract;

THENCE S 73°29'40" E, 50.00 feet, with the north boundary line of said 48.91 acre tract and with the south boundary line of said Big Valley Lane, to a ½ inch iron rod found for the southeast corner of said Big Valley Lane and for the southwest corner of a called 8.09 acre tract of land described by a deed to ANN THI THANH NGUYEN & LOI NGOC BUI NGUYEN, recorded in Document No. 2025016922, of said Property Records, and for the northeast corner of a called 0.095 acre passage easement recorded in Volume 3838, Page 161, Official Public Records of Bell County, Texas;

THENCE with the common boundary line of said passage easement and said 48.91 acre tract for the following courses:

1. S 16°07'21" W, 20.61 feet, to a ½ inch iron rod found at the southwest corner of said passage easement;
2. S 73°18'24" E, 206.23 feet, to a ½ inch iron rod found for the southeast corner of said passage easement and being in the west boundary line of a called 6.321 acre tract described by a deed to IMMANUEL PRAYER HOUSE, INC., recorded in Volume 3838, Page 161, of said Public Records;

THENCE with the east boundary line of said 48.91 acre tract for the following courses:

1. S 16°58'04" W, 297.23, with the west boundary line of said 6.321 acre tract, to a ½ inch iron rod found at the southwest corner of said 6.321 acre tract and for the northwest corner of a called 5.1 tract of land described by a deed to IMMANUEL PRAYER HOUSE, INC., recorded in Document No. 2021006851, of said Property Records;

2. S 00°23’33” W, 521.17 feet, with the west boundary line of said 5.1 acre tract and with the west boundary line of a called 12.44 acre tract of land described by a deed to MICHAEL JOHN AUSTIN, recorded in Document No. 2025015769, of said Property Records, to a ½ inch iron rod found;
3. S 09°12’04” E, 200.53 feet, to a ½ inch iron rod found for an easterly corner of a called 24.02 acre tract of land described by a deed to THE TRUE VINE, LC, recorded in Volume 5760, Page 299, of said Public Records;

THENCE with the common boundary line of said 48.91 acre tract and said 24.02 acre tract for the following courses:

1. S 80°47’56” W, 20.00 feet, to a ⅜ inch iron rod found;
2. N 09°12’04” W, 202.21 feet, to a ⅜ inch iron rod found;
3. N 00°23’30” E, 337.94 feet, to a 1-inch iron pipe found;
4. N 89°59’07” W, 34.75 feet, to a 1-inch iron pipe found;
5. N 00°01’24” E, 24.96 feet, to a 1-inch iron pipe found;
6. N 89°45’45” E, 34.91 feet, to a 1-inch iron pipe found;
7. N 00°23’30” E, 163.13 feet, to a ⅜ inch iron rod found;
8. N 82°22’06” W, 228.45 feet, to an 18-inch diameter oak tree found;
9. S 26°52’12” W, 92.76 feet, to a cedar fence post found;
10. S 35°26’14” W, 96.79 feet, to a ⅜ inch iron rod found;
11. S 30°32’02” W, 150.54 feet, to a ½ inch iron rod found;
12. S 22°37’15” W, 138.35 feet, to a ⅜ inch iron rod found;
13. S 44°04’50” W, 6.86 feet, to a ⅜ inch iron rod found;
14. S 79°50’30” W, 44.38 feet, to an 18-inch diameter elm tree;
15. S 77°56’34” W, 31.41 feet, to an 12-inch diameter cedar tree;
16. S 64°26’57” W, 79.72 feet, to an iron railroad spike found in the base of a cedar tree stump;
17. S 16°20’39” W, 1381.46 feet, to a 1-inch iron pipe found for the southeast corner of said 48.91 acre tract and being at the southwest corner of said 24.02 acre tract and being in the north boundary line of a called 173.849 acre tract of land described by a deed to PETER ANDREW LOWRY ET AL., recorded in Document No. 2022038486, of said Public Records, for the most southerly corner of this tract;

THENCE N 74°18’05” W, 786.73 feet, with the south boundary line of said 48.91 acre tract and along the north boundary line of said 173.849 acre tract, to a 60D nail found at the base of a cedar fence post for the southwest corner of said 48.91 acre tract and being at the southeast corner of a called 74.37 acre tract of land described by a deed to DINNA MARIE HAMILTON, recorded in Volume 2291, Page 568, of said Public Records, for the southwest corner of this tract;

THENCE with the west boundary line of said 48.91 acre tract and along the east boundary line of said 74.37 acre tract for the following courses:

1. N 15°15’02” E, 2122.71 feet, to a ½ inch iron rod found;
2. S 82°48’01” E, 6.12 feet, to a 60D nail found at the base of a cedar fence post;

3. N 14°20'35" E, 194.66 feet, to a ½ inch iron rod found at the southwest corner of a called 1 acre tract of land described by a deed to JOSE RODRIGUEZ, recorded in Document No. 2013007988, of said Property Records, for a northwesterly corner of this tract;

THENCE S 73°05'57" E, 562.68 feet, with the north boundary line of said 48.91 acre tract and along the south boundary line of said 1 acre tract and along the south boundary line of a called 9.096 acre tract of land described by a deed to JOSE & ROSA C. RODRIGUEZ, recorded in Document No. 2008037571, of said Property Records, and along the south boundary line of a called 10.0 acre tract of land described by a deed to CAROLINE & SALLY JOHNSON, recorded in Volume 2480, Page 64, of said Public Records, to a ½ inch iron rod found at the southeast corner of said 10.0 acre tract and for the southwest corner of said 20.00 acre tract;


THENCE N 16°57'50" E, 1653.87 feet (*deed: N 16°58'05" E, 1653.92'*), with the west boundary line of said 20.00 acre tract and along the east boundary line of said 10.0 acre tract, to a ½ inch iron rod found in the south right-of-way line of said F.M. Road 2410, for the northwest corner of said 20.00 acre tract and being at the northeast corner of said 10.0 acre tract, for the most northwesterly corner of this tract;

THENCE N 79°10'40" E, 552.03 feet (*deed: N 79°11'15" E, 551.95'*), with the north boundary line of said 20.00 acre tract and with the south right-of-way line of said F.M. Road 2410, to the **POINT OF BEGINNING** and containing 68.90 acres of land.

NOTES:
The bearings recited herein are grid bearings derived from GPS observations based on the NAD 1983 (2011 datum) State Plane Coordinate System, Texas Central Zone (4203). All distances are horizontal ground distances.

Luther E. Frobish 08/19/2026
Luther E. Frobish
Registered Professional Land Surveyor
State of Texas No. 6200





PRELIMINARY PLAT

THE SANCTUARY AT HARKER HEIGHTS

An addition to the City of Harker Heights, Bell County, Texas

68.90 acres, 5 blocks, 106 lots, 3 tracts

SHEET 2

Point of Beginning
capped iron rod found

F.M. ROAD 2410
(100' R.O.W.)

Approximate limits of
ZONE A
FEMA FIRM
#48027C0325E
eff. 09/26/2008

JDCB SERIES LLC-SERIES
A-KNIGHTS GARDEN HOME LLC
14.909 ACRES
DOC. #2023031944

BEVERLY ANN BRUNSON ET AL.
6.63 ACRES
DOC. #2021071031

BEVERLY ANN
BRUNSON ET AL.
2.000 ACRES
VOL. 2219, PG. 292
DOC. #2021071031

BIG VALLEY LANE (50' R.O.W.)

BEVERLY ANN BRUNSON ET AL.
22.93 ACRES
DOC. #2021071031

CAROLINE &
SALLY JOHNSON
10.0 ACRES
VOL. 2480, PG. 64

JOSE & ROSA C.
RODRIGUEZ
9.096 ACRES
DOC. #2008037571

ANN THI THANH NGUYEN
& LOI NGOC BUI NGUYEN
8.09 ACRES
DOC. #2025016922

PASSAGE EASEMENT
0.095 ACRE
VOL. 3838, PG. 161

JOSE RODRIGUEZ
1 ACRE
DOC. #2013007988

IMMANUEL PRAYER HOUSE, INC.
6.321 ACRES
VOL. 3838, PG. 161

IMMANUEL PRAYER HOUSE, INC.
5.1 ACRES
DOC. #2021006851

MICHAEL JOHN AUSTIN
12.44 ACRES
DOC. #2025015769

SHEET 2

DINNA MARIE HAMILTON
74.37 ACRES
VOL. 2291, PG. 568

THE TRUE VINE, LC
24.02 ACRES
VOL. 5760, PG. 299

THE TRUE VINE, LC
24.02 ACRES
VOL. 5760, PG. 299

PETER ANDREW LOWRY ET AL.
173.849 ACRES
DOC. #2022038486

SHEET 3

REPUBLIC
ENGINEERING & DEVELOPMENT SERVICES


FROBISH
LAND SURVEYING

SHEET INDEX:

SHEET 1 - COVER SHEET, VICINITY MAP, & FULL BOUNDARY
SHEET 2 - SUBDIVISION LOT LAYOUT, CURVE TABLE & GENERAL NOTES
SHEET 3 - SUBDIVISION LOT LAYOUT & SIGNATURES

0 100' 200'
SCALE: 1" = 200'

DO NOT RECORD
PRELIMINARY PLAT FOR
REVIEW PURPOSES ONLY



PRELIMINARY PLAT

THE SANCTUARY AT HARKER HEIGHTS

An addition to the City of Harker Heights, Bell County, Texas

68.90 acres, 5 blocks, 106 lots, 3 tracts

LEGEND:

- 8 / 8400 = LOT NUMBER/SQUARE FEET
- 4 = BLOCK NUMBER
- D.E. = DRAINAGE EASEMENT
- R.O.W. = RIGHT-OF-WAY
- U.E. = UTILITY EASEMENT
- ● = ½" IRON ROD FOUND (unless otherwise noted)
- ⊙ = 1" IRON PIPE FOUND

GENERAL NOTES:

1. THE BEARINGS RECITED HEREON ARE GRID BEARINGS DERIVED FROM GPS OBSERVATIONS BASED ON THE NAD83(2011) STATE PLANE COORDINATE SYSTEM, TEXAS CENTRAL ZONE NO. 4203. ALL DISTANCES ARE HORIZONTAL GROUND DISTANCES. THE COMBINED SCALE FACTOR (CSF) = 1.0001533.
2. A PORTION OF THIS TRACT IS SHOWN TO BE WITHIN A *ZONE A* (100-YEAR FLOOD ZONE), PER FEMA'S FLOOD INSURANCE RATE MAP (FIRM) FOR BELL COUNTY, TEXAS, PANEL NUMBER 48027C0325E, EFFECTIVE 09/26/2008. THIS DOES NOT IMPLY THAT THIS TRACT WILL, OR WILL NOT FLOOD, NOR DOES IT CREATE ANY LIABILITY IN SUCH EVENT ON THE PART OF THIS SURVEYOR.
3. BUILDING SETBACK LINES PER THE CITY OF HARKER HEIGHTS ZONING DISTRICT REGULATION 155.020 R-1 ONE-FAMILY DWELLING DISTRICT ARE AS FOLLOWS: FRONT = 20', EXCEPT FOR FRONT ENTRY GARAGES AND CARPORTS WHICH SHALL BE 25', CORNER = 15', SIDE = 6', REAR = 20'
4. FIELD NOTES ACCOMPANY THIS PLAT.
5. WATER AND SEWER SERVICES FOR THIS TRACT WILL BE PROVIDED BY THE CITY OF HARKER HEIGHTS.
6. ELECTRIC SERVICE FOR THIS TRACT IS PROVIDED BY ONCOR ELECTRIC DELIVERY.
7. ALL TRACTS ARE TO BE OWNED AND MAINTAINED BY THE HOA.
8. LOT 27 BLOCK 5 SHALL BE A DRAINAGE TRACT OWNED AND MAINTAINED BY THE HOA.

CURVE TABLE:

CURVE	RADIUS	ARC LENGTH	CHORD BEARING	CHORD LENGTH
C1	30.00'	47.12'	N 61°57'12" E	42.43'
C2	60.00'	44.30'	N 85°48'05" E	43.30'
C3	60.00'	49.95'	N 40°48'05" E	48.52'
C4	30.00'	47.12'	N 61°57'12" E	42.43'
C5	60.00'	13.71'	S 79°35'41" E	13.68'
C6	60.00'	50.93'	N 69°32'30" E	49.41'
C7	60.00'	29.61'	N 31°05'22" E	29.31'
C8	30.00'	47.12'	S 61°57'12" W	42.43'
C9	60.00'	9.28'	N 77°28'42" W	9.27'
C10	60.00'	49.19'	S 74°36'15" W	47.82'
C11	60.00'	35.78'	S 34°02'08" W	35.25'
C12	200.00'	51.19'	N 09°37'13" E	51.06'
C13	170.00'	43.52'	S 09°37'13" W	43.40'
C14	230.00'	58.87'	S 09°37'13" W	58.71'
C15	62.00'	94.69'	S 15°01'25" E	85.75'
C16	62.00'	75.92'	S 63°48'26" W	71.27'
C17	62.00'	156.32'	N 08°52'56" W	118.08'


0 50' 100'

SCALE: 1" = 100'

DO NOT RECORD
PRELIMINARY PLAT FOR REVIEW PURPOSES ONLY

REPUBLIC ENGINEERING & DEVELOPMENT SERVICES

FROBISH LAND SURVEYING



LEGEND:

8 / 8400	= LOT NUMBER/SQUARE FEET
4	= BLOCK NUMBER
D.E.	= DRAINAGE EASEMENT
R.O.W.	= RIGHT-OF-WAY
U.E.	= UTILITY EASEMENT
•	= ½" IRON ROD FOUND (unless otherwise noted)
⊙	= 1" IRON PIPE FOUND

PRELIMINARY PLAT
THE SANCTUARY AT HARKER HEIGHTS
An addition to the City of Harker Heights, Bell County, Texas
68.90 acres, 5 blocks, 106 lots, 3 tracts

OWNER/DEVELOPER:
C.A. DOOSE & COMPANY, LLC
800 KENNEDY COURT
BELTON, TX 76513

ENGINEER:
REPUBLIC ENGINEERING & DEVELOPMENT SERVICES
PO BOX 1146
BELLVILLE, TX 77418

SURVEYOR:
FROBISH LAND SURVEYING, LLC
P.O. BOX 1411
BELTON, TX 76513

KNOW ALL MEN BY THESE PRESENTS, THAT C.A. DOOSE & COMPANY, LLC, BEING THE SOLE OWNER OF THAT CERTAIN 68.90 ACRE TRACT OF LAND IN THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS, SITUATED IN THE JAMES M. CROSS SURVEY, ABSTRACT NO. 179 AND THE W.H. WEBB SURVEY, ABSTRACT NO. 1016, BELL COUNTY, TEXAS, AND BEING ALL OF A CALLED 20.00 ACRE TRACT OF LAND AS DESCRIBED BY A DEED TO SAID OWNER, RECORDED IN DOCUMENT NO. 2022017402, REAL PROPERTY RECORDS IN BELL COUNTY, TEXAS, AND BEING ALL OF A CALLED 48.91 ACRE TRACT OF LAND AS DESCRIBED BY A DEED TO SAID OWNER, RECORDED IN DOCUMENT NO. 2021051936, OF SAID PROPERTY RECORDS, WHICH IS MORE FULLY DESCRIBED IN THE DEDICATION OF SAID OWNER AS SHOWN BY THE PLAT HEREOF, ATTACHED HERETO, AND MADE A PART HEREON, AND APPROVED BY THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS AND THE SANCTUARY AT HARKER HEIGHTS DOES HEREBY DEDICATE TO SAID CITY ALL STREETS, AVENUES, DRIVES, ALLEYS SHOWN ON SAID PLAT, THE SAME TO BE USED AS PUBLIC THOROUGHFARES AND FOR THE INSTALLATION AND MAINTENANCE OF PUBLIC UTILITIES WHEN AND AS AUTHORIZED BY THE CITY OF HARKER HEIGHTS.

THE DRAINAGE AND UTILITY EASEMENTS SHOWN ON SAID PLAT ARE DEDICATED FEE SIMPLE TO SAID CITY OF HARKER HEIGHTS FOR INSTALLATION AND MAINTENANCE OF ANY AND ALL PUBLIC UTILITIES, WHICH THE CITY MAY ELECT TO INSTALL AND MAINTAIN OR PERMIT TO BE INSTALLED OR MAINTAINED.

WITNESS THE EXECUTION HEREOF, ON THIS _____DAY OF _____, 20____.

FOR: C.A. DOOSE & COMPANY, LLC

BY: _____
CRAIG LANGFORD, AGENT

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY, PERSONALLY APPEARED CRAIG LANGFORD KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT. IT HAS BEEN ACKNOWLEDGED TO ME THAT HE EXECUTED THE FOREGOING INSTRUMENT AS THE OWNERS OF THE PROPERTY DESCRIBED HEREON.

_____
NOTARY PUBLIC STATE OF TEXAS
MY COMMISSION EXPIRES: _____

PLANNING

APPROVED THIS _____ DAY OF _____, 20____ , A.D. BY THE DIRECTOR OF PLANNING AND DEVELOPMENT OF THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS.

_____
DIRECTOR OF PLANNING AND DEVELOPMENT

PLANNING AND ZONING COMMISSION

APPROVED THIS _____ DAY OF _____, 20____ , A.D. BY THE PLANNING AND ZONING COMMISSION OF THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS.

_____ _____
CHAIRPERSON, PLANNING AND ZONING COMMISSION — SECRETARY, PLANNING AND ZONING COMMISSION

CITY COUNCIL

APPROVED THIS _____ DAY OF _____, 20____ , A.D. BY THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS.

_____ _____
MAYOR — CITY SECRETARY

SURVEYORS' CERTIFICATE:

THAT I, LUTHER E. FROBISH, DO HEREBY CERTIFY THAT I PREPARED THIS PLAT FROM AN ACTUAL AND ACCURATE SURVEY OF THE LAND AND THAT THE CORNER MONUMENTS SHOWN THEREON WERE PROPERLY PLACED UNDER MY PERSONAL SUPERVISION, IN ACCORDANCE WITH THE SUBDIVISION AND PROPERTY DEVELOPMENT REGULATIONS OF THE CITY OF HARKER HEIGHTS, TEXAS.

_____
LUTHER E. FROBISH
REGISTERED PROFESSIONAL LAND SURVEYOR
STATE OF TEXAS NO. 6200

DO NOT RECORD
PRELIMINARY PLAT FOR REVIEW PURPOSES ONLY

STATE OF TEXAS · REGISTERED · LUTHER E. FROBISH · 6200 · PROFESSIONAL · LAND SURVEYOR

REPUBLIC ENGINEERING & DEVELOPMENT SERVICES

FROBISH LAND SURVEYING

THE SANCTUARY AT HARKER HEIGHTS

P26-14 – The Sanctuary at Harker Heights – Preliminary Plat

Plat Distributed to HH Staff & Public Utilities: 10/5/2026
Comments Sent to Applicant: 10/19/2026

No Response To Date – Comments may be forthcoming
Oncor
Atmos
Brightspeed
KISD
Fire Department

TXDOT – TxDOT has no comments at this time; however, TxDOT will continue to work with the developer to ensure the appropriate mitigation measures are incorporated into the project.

Planning & Development

1. Title block should include the current legal description (or reference thereto) date of survey, and date of preparation. This title block shall be present on each page of the plat.

Building Official

1. § 158.10 Floodplain Management. (C) Coordination of City of Harker Heights and FEMA floodplain delineations. For all subdivisions developed adjacent to or within non-detailed designated FEMA floodplains, the applicant/ developer shall be required to provide a detailed study to determine the Base Flood Elevations (BFEs) for all lots that are adjacent or within the non-detailed area. The BFEs must be developed using approved FEMA guidelines and methods. A copy is to be furnished to the city prior to final plat.
2. § 154.37 (A) (3) Per Public works comments, the proposed entrance to the subdivision must meet the requirements as a collector and each lane must be a minimum of 24' wide.

Public Works

1. Indicate all Public Utility Easements meet the minimum 15' width requirement for water and sanitary sewer utilities (§ 154.42(A)(1)). 15' Easements for Sanitary Sewer Utilities noted. 10' PUE's were indicated on submitted plans for Water Utilities.
2. Provide a street and sidewalk layout plan that includes the proposed street names (§ 154.2(C)(2)(D). Only one street name "Big Valley Lane" was noted on the submitted plans.

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

DISCUSS AND CONSIDER APPROVING A FINAL PLAT REFERRED TO AS RANGER TOP ADDITION FINAL PLAT, A 1.003 ACRE, SITUATED IN THE ELIZABETH DAWSON SURVEY, ABSTRACT 258, BELL COUNTY, TEXAS, AND BEING ALL OF THAT CERTAIN TRACT DESCRIBED AS 1.0 ACRE IN A GENERAL WARRANTY DEED WITH VENDOR'S LIEN, TO RANGER TOP, LLC., RECORDED IN DOCUMENT NO. 2022004499, OFFICIAL PUBLIC RECORDS OF REAL PROPERTY, BELL COUNTY, TEXAS. (PLANNING ADMINISTRATOR)

EXPLANATION:

REFERENCES:
Case #P26-13
MGO #2026-213

The applicant submitted an application for a Final Plat referred to as Ranger Top Addition Final Plat for a 1.003 acre tract of land located at 1829 E. Knights Way. The purpose of this Final Plat is to create 1 commercial lot.

Per the Bell County Tax Appraisal District, since 1977 there has been a structure on this parcel consisting of approximately 1,280 square feet. This property was then annexed into the City in 1988. The parcel is zoned B-3 (Local Business District) and the current Land Use Plan designates this parcel for Regional Commercial Center use. The applicant intends to utilize this parcel as a convenience store/gas station, which is consistent with the current zoning.

On January 23, 2023, a Preliminary Plat application was submitted and was withdrawn prior to consideration by the Planning & Zoning Commission and City Council.

On April 4, 2025, a Preliminary Plat application was submitted and was conditionally approved by the Planning & Zoning Commission and City Council with the following condition:

- All outstanding comments shall be addressed and resolved as directed by staff prior to the release of infrastructure permits and/or the submission of the Final Plat.

On October 1, 2026, a Final Plat application was submitted. Staff reviewed the submitted plat documents and on October 14, 2026, provided comments related to safety and compliance with applicable development regulations outlined in the City of Harker Heights Code of Ordinances.

As of October 21, 2026, comments are still outstanding; see attachment titled:

- "P26-13_CombinedComments_RangerTop_(MGO 2026-213) - 10-14-26"

Any additional submittals and corresponding comments will be provided to the City Council at the time of the meeting.

Particular attention during the review of final plats is given to the arrangement, location, and width of streets and access easements; their relationship to the topography; utility infrastructure including water, wastewater, and drainage; the coordination with future development of adjacent properties; and compliance with applicable city ordinances, policies, and plans.

RECOMMENDATION:

The Planning & Zoning Commission will meet on October 28, 2026 to consider approval of this plat. At the time this staff report was created, the Planning & Zoning Commission had not held its meeting. Staff will provide the Planning & Zoning Commission's recommendation and staff's recommendation at the City Council meeting.

ACTION BY THE CITY COUNCIL:

1. Motion to **approve** of a request for a Final Plat referred to as Ranger Top Addition Final Plat, as read in the caption by the Mayor, based on the **discussed** recommendations and findings.
2. Motion to **approve with condition** of a request for a Final Plat referred to as Ranger Top Addition Final Plat, as read in the caption by the Mayor, based on the **discussed** recommendations and findings. with the following condition(s):
    a. All comments shall be addressed as directed by staff prior to the recordation of the Final Plat.
3. Motion to **disapprove with explanation** of a request for a Final Plat referred to as Ranger Top Addition Final Plat, as read in the caption by the Mayor, based on the **discussed** recommendations and findings**with the following explanation: Applicant has not met the requirements of §154: SUBDIVISIONS**
4. Any other action desired.

ATTACHMENTS:

P26-13_Final Plat Application
P26-13_Final Plat Checklist
P26-13_Location
P26-13_Dedication
P26-13_Field Notes
P26-13_Final Plat
P26-13_Preliminary Construction Plan Sheets
P26-13_CombinedComments_RangerTop_ (MGO 2026-213) - 10-14-26

Final Plat Application

City of Harker Heights
Planning & Development
305 Miller's Crossing
Harker Heights, TX 76548
Phone: (254) 953-5647
Email:
planning@harkerheights.gov

Requirements - APPLICATION MUST BE FULLY COMPLETED OR WILL NOT BE ACCEPTED

This application must be completed and returned to the Planning and Development Department of the City of Harker Heights, Texas along with the following:

1. **Payment per the most recently approved fee schedule**
2. **Signed Original Field Notes and Dedication Pages**
3. **Paper Plan Submissions: Ten (10) Copies of Plat and Seven (7) sets of Final Engineering Plans**
4. **Electronic Submissions: Plat and Engineering Plans submitted to department email in PDF format.**
5. **Completed Final Plat Checklist**

Property Information:

Plat Name: Ranger Top Addition Date Submitted: 09/04/2026

Number of Lots: 1 Number of Units/Suites: 1 Acreage: 1.003

Site Address or General Location: 1829 East F.M. 2410 Road Harker Heights Texas 76513

○ Residential ☑ Commercial ○ Both On Site Detention Proposed with Subdivision: ☑ Yes ○ No ○ Other

Date of Preliminary Plat Approval by P&Z: May 14, 2025

Owner Information & Authorization:

Property Owner: Ranger Top LLC

Address: 3913 Hickory View Harker Heights Texas, 76548

Phone: _____ E-Mail: cp.paudel@gmail.com

Developer: _____

Address: _____

Phone: _____ E-Mail: _____

Engineer: Om Gharty Chhetri, P.E.

Address: 1001 W. Euless Boulevard Suite 412H

Phone: _____ E-Mail: omgc@icivileng.com

Surveyor: Brett A. Butts, R.P.L.S.

Address: 4330 South 5th Street Temple TX

Phone: _____ E-Mail: brett@allcountysurveying.com

For more information reference Section 154.22 Final Plat of the Harker Heights Code of Ordinances

I HEREBY UNDERSTAND AND ACKNOWLEDGE:

The final plat must be prepared in accordance with the City's subdivision rules and regulations and shall conform substantially to preliminary plat layout as approved. The subdivider will be required to install at his/her own expense all water lines, streets, sewer lines, drainage facilities, and structures within the subdivision accords to Section 154.36 of the Harker Heights Code of Ordinances.

All required improvements must be completed unless a Bond or Letter of Credit has been posted and attached in sufficient amount to assure completion.

A maintenance bond/surety instruments has been furnished to assure the quality of materials and workmanship and maintenance of all required improvements including the City's cost for collecting the guaranteed funds and administering the correction and/or replacement of covered improvements in the even the subdivider defaults.

The maintenance bond or other surety instrument shall be satisfactory to the city as to form, sufficiency and manner of execution. For water and sewer related improvements, the bond or other instrument shall be in an amount equal to 20% of the cost of improvements verified by the city Engineer and shall run for a period of one calendar year. Bonds or other instruments for streets and drainage facilities shall be in an amount equal to 40% of the improvements verified by the city Engineer and shall run for a period of two calendar years.

The applicant or their authorized representative must be present at all Planning and Zoning Commission and City Council Meetings at which their plat is on the agenda for discussion or action. Failure of the applicant or their authorized representative to appear before the Planning and Zoning Commission or City Council during a meeting on which their plat is on the agenda for discussion or action may be deemed a withdrawal of their plat.

	BRETT A. BUTTS, ALL COUNTY SURVEYING
Printed Name of Owner	**Printed Name of Authorized Agent (Corporation/Partnership)**
Signature of Owner	**Signature of Authorized Agent (Corporation/Partnership)**

SWORN AND SUBSCRIBED BEFORE ME THIS 4th *DAY OF* September, 20 26.

Signature of Notary Public

JUSTIN S. MYERS
Notary Public, State of Texas
Comm. Expires 04-13-2027
Notary ID 131971188

My Commission Expires: 04-13-2027

STAFF ONLY – DO NOT FILL OUT

Date Submitted: _____ Received By: _____ Case #: _____ Receipt #: _____

Rev. 12/22

For Office Use Only

Project # _____

Final Plat/ Replat/ Minor Plat/ Amending Plat Checklist

The following is a partial listing of requirements for Final Plat, Replat, Minor Plat, and Amending Plat applications as found in the City of Harker Heights' Code of Ordinances and policies. A completed checklist must be submitted with each application. All applications are required to be submitted via the City's online portal at https://www.mygovernmentonline.org/. Applications are only accepted on the dates indicated in the adopted annual intake calendar (https://harkerheights.gov/index.php/boards-and-commissions/planning-and-zoning/p-z-commission). Applicants shall indicate compliance with standards by checking the box adjacent to the standard. Failure to comply with standards could result in rejection of application, delay of Final Plat, Replat, Minor Plat, and Amending Plat approval, and/or disapproval. This checklist is in accordance with §154.20(A)(1) and §154.22 of the City's Code of Ordinances.

Section 1 – General Provisions *(check if provided; indicate NA if not applicable)*

Please clarify the status of this Final Plat/Replat/Minor Plat/ Amending Plat (Plat) submittal:

☐ **1.1** A pre-application meeting with the City's Development Review Committee has been held for this Plat area. **(§154.20(A)(1)(a))**

Date of Meeting: _____.

☐ **1.2** A Concept Plan was previously approved /conditionally approved for this Plat area. **(§154.20(A)(2))**

Date of Approval: _____; Case Number: _____.

☐ **1.3** Concurrent filing of this Plat with a Concept Plan was approved in writing by the Planning & Development Director. **(§154.20(A)(2)(e))**

Date of Approval: _____.

☑ **1.4** A Preliminary Plat was previously approved /conditionally approved for this Plat area. **(§154.20(A)(3))**

Date of Approval: May 14, 2025; Case Number: P25-07/MGO#2025-110.

Section 1 – General Provisions cont. *(check if provided; indicate NA if not applicable)*

☐ **1.5** Concurrent filing of this Plat with a Preliminary Plat was approved in writing by the Planning & Development Director.

Date of Approval: _____.

☐ **1.6** This is a replat of a previously approved Final Plat.

Name of original Final Plat: _____.

Date original Final Plat was approved: _____.

Change in the number of Lots from _____ to _____.

☑ **1.7** Total area for this Plat is: 1.003 (acres); 43690.68 (square feet).

☑ **1.8** Current Zoning District(s) for this Plat area is:

B-3.

☑ **1.9** Number of Lots/Tracts/Remainders Per respective Zoning District in this Plat area is:

1.

Section 2 – Legal *(check if provided; indicate NA if not applicable)*

☑ **2.1** Provide a completed application form and fees. **(§154.20(B)(1-2))**

☑ **2.2** Provide proof of ownership for the Plat area. **(§154.20(A))**

- Copy of deed
- For businesses, non-profits, etc. provide signed documentation authorizing applicant to sign on behalf of the entity. **(§154.20(A)(6))**

☐ **2.3** Provide a copy of recorded documentation for existing easements.

Section 3 – General Plat Standards *(check if provided; indicate NA if not applicable)*

☑ **3.1** Provide an exact digital copy of the submitted/revised Final Plat. **(§154.20(B)(3)(c) and §154.20(B)(6))**

- DXF, DWG, or GIS Shapefile/feature class / coverage format.
- Based of State Plane 83 Texas South Central Zone 4204 coordinate system.

Section 3 – General Plat Standards cont. *(check if provided; indicate NA if not applicable)*

☑ **3.2** Provide an exact digital copy, three full sized hard copy and a half-sized hard copy of the public infrastructure As-Built drawings. **(§154.20(B)(3)(c), §154.20(B)(6), and §154.25))**

- DXF, DWG, or GIS Shapefile/feature class / coverage format.
- Based of State Plane 83 Texas South Central Zone 4204 coordinate system.
- All requirements stated in **§154.25** shall be met in the submitted as-builts.

☑ **3.3** Provide two hard copies of the Plat and engineering drawings. **(§154.20(B)(3)(b) and §154.22(B))**

- Hard copies are legible such that they can be clearly reproduced.
- Line types and weights are clearly identifiable in black and white and upon reproduction.
- Abandonments are indicated with shading or hatching and are labeled “To be abandoned by this plat.”.
- ROW dedication is indicated with a unique shading or hatching and are labeled.

☑ **3.3** Plat is sealed by a Texas Licensed Professional Engineer or Texas Registered Professional Land surveyor. **(§154.22(B)(1))**

☑ **3.4** Sheet sizes shall be a 22” x 34” black and white drawing in landscape view at a scale of 1-inch = 100 feet. **(§154.21(B)(1))**

☑ **3.5** If submitting three or more sheets, provide a cover sheet with table of contents and a vicinity map that clearly shows the project’s location. **(§154.22(B)(1)(a))**

- The vicinity map shall be at a scale such that it is easy to determine what part of the city the project is located (major road name(s)).

☑ **3.6** Title block on each page includes: the proposed subdivision name, phase(s), block numbers, lot numbers, current legal description, acreage, name/address of property owner, name/address of surveyor, name/address of engineer, date of survey, date of preparation, page content title. **(§154.22(B)(1)(b))**

☑ **3.7** Index Sheet at 1-inch = 100 feet is provided if applicable. **(§154.22(B)(1)(d))**

☑ **3.8** A north arrow is required on all sheets and should be oriented either upward or to the right. **(§154.22(B)(1)(o))**

- Orient the plan sheets such that north is toward the top or left-hand side of the sheet.

Section 4 – Plat Standards *(check if provided; indicate NA if not applicable)*

☑ **4.1** Provide legal description, existing boundary, lot lines and right-of-way lines of streets and easements with accurate dimensions, bearings, deflection angles, radii, and central angles of all curves. **(§154.22(B)(1)(c), §154.22(B)(3) and §154.26)**

- Label and illustrate all of the above items. This includes current and proposed configurations for replats, minor plats and amending plats.
- The applicant will furnish the city with a signed, original copy of the dedication, resolution, and field notes.
- Provide enough information for easements shall be such that they can be found in the field with the plans.
- Label types and dimensions of easements (proposed, existing, utility, drainage, access, etc.)

☑ **4.2** Lot lines shall have line dimensions clearly displayed within the lot along with the lot’s respective lot number. Groups of lots that are considered within a block shall have the block number clearly displayed. **(§154.22(B)(1)(e))**

Section 4 – Plat Standards cont. *(check if provided; indicate NA if not applicable)*

- [x] **4.3** All right-of-way lines and easements shall be clearly displayed on the plat. The plat shall clearly display the location, size, and purpose of all existing and proposed easements on or adjoining the property. **(§154.22(B)(1)(f))**
- [x] **4.4** Location of existing and proposed streets, alleys, bikeways, and sidewalks on or adjoining the site. Such information shall include name, right-of-way widths, type and width of surfacing. All private streets shall be clearly labeled. **(§154.22(B)(1)(g))**
- [x] **4.5** Identify (illustrate and label) any areas reserved or dedicated for public use. **(§154.22(B)(1)(h))**
- [ ] **4.6** Provide notes addressing how lots with low wastewater service tolerances will be served. **(§154.22(B)(1)(i))**
- [x] **4.7** Delineation of the Federal Emergency Management Association (FEMA) Special Flood Hazard Area as well as any hazards from adjacent detention facilities or as required by the city. **(§154.22(B)(1)(j))**
- [x] **4.8** Identify (illustrate and label) easements and street stub-outs necessary to serve adjacent properties. **(§154.22(B)(1)(k))**
    - Refer to adjacent recorded plats, any recorded easements, the City's plans, the City's Thoroughfare plan, the City's sidewalk plan, the City's Hike and Bike plan and all of the City's various utility Master Plans. **(§154.21(C)(2)(D)(2-3))**
    - TXDOT required marginal access easement.
    - Provide field notes and other documents for offsite easement and/or R.O.W. dedication.
- [x] **4.9** Adjacent property information including present ownership, legal descriptions (recorded volume and page or subdivision Lot and Block) and property lines within 100 feet. **(§154.22(B)(1)(l))**
    - This includes properties across the street from the plat area.
- [x] **4.10** Primary control points or descriptions and ties to such control points to which all dimensions, angles, bearings, and similar data shall be referred. **(§154.22(B)(1)(m))**
- [x] **4.11** The plat shall be located with respect to a corner of the surveyor tract, or an original corner of the original survey of which it is a part. Temporary benchmarks and NGS datum shall be described on each sheet. **(§154.22(B)(1)(m))**
- [x] **4.12** Scale, basis of bearing and benchmarks (datum) and description shall all be clearly displayed on the plat. **(§154.22(B)(1)(n))**
- [x] **4.13** Provide the minimum building setback lines on all lots and other sites. **(§154.22(B)(1)(p))**
- [x] **4.14** All Final Plats, Replats, Minor Plats and Amending Plats shall have affixed to the first page of the plat sheets to be recorded a surveyor's certificate, in the following format **(§154.22(B)(1)(q)(1))**:

KNOW ALL MEN BY THESE PRESENTS:

That I, _____, do hereby certify that I prepared this plat from an actual and accurate survey of the land and that the corner monuments shown thereon were properly placed under my personal supervision, in accordance with the Subdivision and Property Development Regulations of the City of Harker Heights, Texas.

_____

Signature

_____

Texas Reg. No.

Section 4 – Plat Standards cont. *(check if provided; indicate NA if not applicable)*

☑ **4.15** All Final Plats and conditionally approved Final Plats, Replats, Minor Plats and Amending Plats shall have affixed to the first page of the plat sheets to be recorded a certificate of approval by the Planning and Zoning Commission, in the following format **(§154.22(B)(1)(q)(3))**:

Approved this_____day of _____, _____, by the Planning and Zoning Commission of the City of Harker Heights, Texas.

_____

Chairperson, Planning and Zoning Commission

_____

Secretary, Planning and Zoning Commission

☑ **4.16** All Final Plats and conditionally approved Final Plats, Replats, Minor Plats and Amending Plats shall have affixed to the first page of the plat sheets to be recorded a certificate of approval by the City Council, in the following format **(§154.22(B)(1)(q)(4))**:

Approved this_____day of _____, _____, by the City Council of the City of Harker Heights, Texas.

_____

Mayor

_____

City Secretary

☑ **4.17** All Replats, Minor Plats and Amending Plats without conditional approval shall have affixed to the first page of the plat sheets to be recorded a certificate of approval by the Director of Planning and Development, in the following format **(§154.22(B)(1)(q)(5))**:

Approved this_____day of _____, _____, by the Director of Planning and Development of the City of Harker Heights, Texas.

_____

Director of Planning and Development

_____

City Secretary

☑ **4.18** All Final Plats, Replats, Minor Plats and Amending Plats shall have affixed to the first page of the plat sheets to be recorded a tax certificate block, in the following format **(§154.22(B)(1)(q)(6))**:

The Bell County Tax Appraisal District, the taxing authority for all entities in Bell County, Texas, does hereby certify that there are currently no delinquent taxes due or owing on the property described by this plat.

Dated this _____ day of _____, _____, A.D.

Bell County Tax Appraisal District

By: _____

☑ **4.19** All Final Plats, Replats, Minor Plats and Amending Plats shall have affixed to the first page of the plat sheets to be recorded a recordation block, in the following format **(§154.22(B)(1)(q)(7))**:

FILED FOR RECORD this _____ day of _____, _____, in Cabinet _____ , Slide(s)_____, Plat Records of Bell County, Texas. Dedication instrument in Instrument # _____, Deed Records of Bell County, Texas.

Section 4 – Plat Standards cont. *(check if provided; indicate NA if not applicable)*

☑ **4.20** An original certificate of ownership and of dedication of all streets, alleys, easements, and lands to public use forever, signed and acknowledged before a notary public by the owner of the land, shall appear on the face of the Plat, containing complete and accurate description of the property being platted and public dedications. **(§154.22(B)(1)(q)(2))**

Section 5 – Engineering Drawing Standards *(check if provided; indicate NA if not applicable)*

☑ **5.1** Preliminary Engineering Drawings are sealed by a Texas Licensed Professional Engineer. **(§154.22(B)(2))**

☑ **5.2** Sheet sizes shall be a 22” x 34” black and white drawing in landscape view at a scale of 1-inch = 100 feet. **(§154.22(B)(2))**

☑ **5.3** Comply with the standards of design and requirements in the current edition of the North Central Texas Council of Governments’ Standard Specifications for Public Works Construction and the City of Harker Heights’ Code of Ordinances. **(§154.22(B)(2), §154 and Title XV.)**

☑ **5.4** Title block on each page includes: the proposed subdivision name, phase(s), block numbers, lot numbers, current legal description, acreage, name/address of property owner, name/address of surveyor, name/address of engineer, date of survey, date of preparation, page content title. **(§154.22(B)(2)(a))**

☑ **5.5** Lot layout with the area in square feet of each proposed lot annotated. **(§154.22(B)(2)(b))**

☑ **5.6** Provide a Water Layout Plan and details that include locations and labeling of the following **(§154.22(B)(2)(c)):**

- water service connections
- pipe diameters
- valve locations
- fire hydrants
- flush assemblies

☑ **5.7** Provide fire flow and water design sealed explanation and verification that proves fire flow and designed flow that meets state regulatory and technical code requirements can be provided. **(§154.22(B)(2)(c))**

☑ **5.8** Provide a Sewer Layout Plan and profiles that includes details, specifications, and locations and labeling of the following **(§154.22(B)(2)(d) and §154.22(B)(2)(r)):**

- sewer service connections
- pipe diameters
- cleanouts
- manholes & special manholes

☑ **5.9** Provide wastewater system design and lift station capacity sealed explanation and detailed engineering verification that proves designed flow that meets state regulatory and technical code requirements can be serviced. **(§154.22(B)(2)(d))**

Section 5 – Engineering Drawing Standards cont. *(check if provided; indicate NA if not applicable)*

☐ **5.10** Provide Street Plan and profiles that includes paving details, a traffic control plan, and locations and labeling of the following **(§154.21(C)(2)(d)):**

- 9-1-1 approved street names
- roadway classification
- ROW width
- sidewalk width
- alley width (if applicable)
- access easements (passage, trash, etc.)
- fire lanes (if applicable)
- Major thoroughfare plans and profiles shall be drawn at a scale of one inch equals two feet vertically and one inch equals 20 feet horizontally. Minor streets and easement plans and profiles shall be drawn at a scale of one inch equals five feet vertically and one inch equals 50 feet horizontally or one inch equals four feet vertically and one inch equals 40 feet horizontally. Label each plan sheet as to street widths, right-of-way widths, pavement width and thickness, type of roadway materials, curbs, intersection radii, curve data, stationing, existing utilities type and location. Stationing must run from left to right, except for short streets or lines originating from a major intersection where the full length can be shown on a single plan and profile sheet. **(§154.22(B)(2)(m))**

☐ **5.11** Provide a street light layout. **(§154.22(B)(2)(f))**

☑ **5.12** Display natural ground profiles of each right-of-way or easement line. Centerline profiles will be satisfactory for right-of-way or easements, except where there is a difference of 0.50 foot or more from one right-of-way or easement line to the other line measured parallel at any point along the right-of-way or easement. **(§154.22(B)(2)(g))**

☑ **5.13** Provide a Stormwater Drainage Plan that includes locations and labeling of the following **(§154.22(B)(2)(h-k), §154.22(B)(2)(q) and §154.22(B)(2)(r)):**

- Storm water plan and profiles of culverts and channels with specifications and details.
- A grading plan with two-foot contours with delineated drainage basins. Existing contours at intervals of two feet for grades up to 5% and not more than five feet for grades over 5%;
- A drainage/ stormwater design sealed explanation and detailed engineering verification for all stormwater infrastructure that proves no adverse impact and that meets federal & state regulatory requirements, Chapter 158, the adopted Drainage Design Criteria, and technical code requirements.
- A grading, erosion, and sedimentation control plan.
- Details for all stormwater structures to include but not limited to flow line elevations, directional flow, ponds, channels, gully crossings, streams, etc.
- Include FEMA special flood hazard area boundaries (if applicable), FEMA base flood elevations (if applicable), watercourses, railroads, and other physical features on or adjacent to the site.

☑ **5.14** Illustrate and annotate the location and size of all existing and/or proposed city utilities, and all others where known. All city utility lines six inches in diameter or larger within the right-of-way shall be shown on the profile view. All utility lines, regardless of size, should be shown in the plan view, where known. **(§154.22(B)(2)(l))**

Section 5 – Engineering Drawing Standards cont. *(check if provided; indicate NA if not applicable)*

☑ **5.15** Texas Department of Transportation (TXDOT) approvals for driveway and drainage into their jurisdiction, if applicable. **(§154.22(B)(2)(n))**

☑ **5.16** Illustrate and annotate existing conditions such as marshes, wooded areas, buildings, and other significant features. **(§154.22(B)(2)(o))**

☑ **5.17** Illustrate and annotate significant features on adjacent properties such as slopes, structures, and power lines. **(§154.22(B)(2)(p))**

☑ **5.18** Designs conform with the City's engineering standards and specifications, City Ordinances, City Standards, City's plans, the City's Thoroughfare plan, the City's sidewalk plan, the City's Hike and Bike plan and all of the City's various utility Master Plans. **(§154.22(C)(2) and §154.22(B)(2)(r)):**

- Utilize standard engineering scales for the preliminary engineering drawings.
- For special structures and standard details use vertical and horizontal scales that are equal to each other.

☑ **5.19** Station all points of curvature (P.C.'s), point of tangency (P.T.'s) radius returns and grade change point of intersection (P.I.'s) in the profile with their respective elevations. **(§154.22(B)(2)(r))**

Section 6 – Other Requirements (*check if provided; indicate NA if not applicable)*

☑ **6.1** Provide a guarantee of performance, a local unconditional letter of credit, or performance bond for all portions of public infrastructure construction that are not completed at the time of Plat submittal. **(§154.22(B)(4), and §154.23)**

- Sealed Engineer's detailed Opinion of Probable Cost
- Construction Plans for public infrastructure that have been released for construction by the City.

☑ **6.2** Provide any special zoning requirements for those lots within the current City Limits. **(§155)**

- This is typically for parcels with conditional use permits, planned development zoning, or for those within the City's Overlay District.

Ranger Top Addition Location



DEDICATION OF
RANGER TOP ADDITION
within the City of Harker Heights,
Bell County, Texas.

STATE OF TEXAS)
COUNTY OF BELL)

That **RANGER TOP LLC.,** being the sole owner of that certain tract of land containing 1.003 acre described in Field Notes prepared by Brett A. Butts, RPLS No. 6254, dated September 29, 2026 which Field Notes are attached hereto and made a part hereof as fully as if written verbatim, do hereby name and designate said 1.003 acre tract as **RANGER TOP ADDITION,** a subdivision in the City of Harker Heights, Bell County, Texas, and do hereby adopt the attached map and plat thereof and do hereby agree that all future sales and conveyances of said property shall be by reference to said plat and dedication.

RANGER TOP LLC., do hereby give, grant and convey to the **CITY OF HARKER HEIGHTS, TEXAS,** its assignees and franchisees furnishing public utilities in said subdivision, the easements as shown on said plat for drainage and for the installation, operation, maintenance, repair, use and replacement of all public utility lines, including electric power, water, sewer, gas and telephone, and reference is hereby made to such plat for the location of such easements.

To have and to hold said easements unto said Grantee, and the undersigned hereby binds itself, its heirs, administrators, executors, successors and assigns, to warrant and forever defend all and singular said premises unto the said Grantee against every person whomsoever lawfully claiming or to claim the same or any part thereof.

WITNESS THE EXECUTION HEREOF, on this ____ day of _____, 2026.

Ranger Top, LLC.
3913 Hickory View
Harker Heights, Texas 76548

_____

By: Chet P. Paudel, Managing Member

ACKNOWLEDGMENTS

STATE OF TEXAS)
COUNTY OF **BELL**)

BEFORE ME, the undersigned authority, on this day personally appeared **Chet P. Paudel**, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and consideration therein expressed.

GIVEN UNDER MY HAND AND SEAL OF OFFICE on this the ___ day of _____, 2026.

_____
NOTARY PUBLIC, STATE OF TEXAS

AFTER RECORDING, RETURN TO:
All County Surveying, Inc.
4330 South 5th Street
Temple, Texas 76502

FIELD NOTES PREPARED BY ALL COUNTY SURVEYING, INC.

September 29, 2026

Perimeter Description of a **1.003 ACRE,** situated in the **Elizabeth Dawson Survey, Abstract 258,** Bell County, Texas, and being all of that certain tract described as 1.0 acre in a General Warranty Deed with Vendor's Lien, to Ranger Top, LLC., recorded in Document No. 2022004499, Official Public Records of Real Property, Bell County, Texas, and being more particularly described as follows:

BEGINNING at a ½" iron rod with cap stamped "M&ASSOC KILLEEN" found on the north line of F.M. 2410, being the southwest corner of said 1.0 acre tract, same being the southeast corner of a 1.204 acre tract described in a Warranty Deed with Vendor's Lien to Shining Light Investments, LLC, a Texas limited liability, recorded in Document No. 2025060299, of said official public records, for the southwest corner of the herein described tract, from which a ½" iron rod found at the southwest corner of Lot 2, Block 1, W. A. Matkin Subdivision, an addition within the City of Harker Heights, Bell County, Texas according to the plat of record in Cabinet B, Slide 188-B, Plat Records of Bell County, Texas, of said official public records bears *N 88°51'45" W – 830.26';*

THENCE, N 01°09'21" E – 209.41', *(Deed N 03°07'40" E – 208.7'),* to a 1" metal pipe found on the south line of a 3.817 acre tract described in a General Warranty Deed to Hector Ruiz, III, Ryan Enrique Ruiz, and Kaitlin Rene Ruiz, recorded in Document No. 2012-00001602, of said official public records, being the northeast corner of said Lot 1, same being the northwest corner of said 1.0 acre tract, for the northwest corner of the herein described tract, from which a ½" iron rod found at the northwest corner of said 1.204 acre tract bears *N 88°52'32" W – 248.06';*

THENCE, S 88°52'32" E – 239.61', *(Deed S 86°52'20" E – 239.61'),* to a 5/8" iron rod with cap stamped "ACS" set on the west line of Warriors Path Road, being the southeast corner of said 3.817 acre tract, same being the northeast corner of said 1.0 acre tract, for the northeast corner of the herein described tract;

THENCE, with the western line of said Warriors Path Road, the following two (2) courses and distances:

1. **S 14°32'48" W – 164.63',** *(Deed S 16°30'00" W – 165.36'),* to a 2" metal post with "Surveyed" etched in concrete found at the most easterly southeast corner of said 1.0 acre tract, for the most easterly southeast corner of the herein described tract;

2. **S 52°54'08" W – 79.70',** *(Deed S 55°26'30" W – 78.4'),* to a 5/8" iron rod with cap stamped "ACS" set at the intersection of the west line of Warriors Path Road and the north line of F.M. 2410, being the most southerly southeast corner of said 1.0 acre tract, for the most southerly southeast corner of the herein described tract;

THENCE, N 88°51'45" W – 138.90', *(Deed N 86°52'20" W – 138.90'),* with the north line of said F.M. 2410, to the **POINT OF BEGINNING** and containing 1.003 acre of land, more or less, in Bell County, Texas.

The bearings cited hereon are based on grid north of the Texas Coordinate System of 1983, Central Zone, as derived from GPS observations. Distances cited hereon are expressed in US Survey Feet as measured horizontally along the surface of the earth. The combined correction factor (CCF) for this project is 0.99985175, scaled about CP-100 (N:10,356,621.92 E:3,142,239.26).This document is not valid for any purpose unless signed and sealed by a Registered Professional Land Surveyor.

Fieldwork completed March 11, 2026. Surveyed under the direction and supervision of the undersigned:

ALL COUNTY SURVEYING, INC.
1-800-749-PLAT
TX. Firm Lic. No. 10023600
server/projects /pro220000/221300/221372/221372.doc

STATE OF TEXAS
REGISTERED
BRETT A. BUTTS
6254
PROFESSIONAL
LAND SURVEYOR

9/29/2026

Brett A. Butts
Registered Professional Land Surveyor
Registration No. 6254

FINAL PLAT of

RANGER TOP ADDITION

a subdivision within the City of Harker Heights, Bell County, Texas.

1.003 Acres, situated in the Elizabeth Dawson Survey, Abstract 258, Bell County, Texas, being all of that certain tract described as 1.0 acre in a General Warranty Deed with Vendor's Lien, to Ranger Top, LLC., recorded in Document No. 2022004499, Official Public Records of Real Property, Bell County, Texas.

STATE OF TEXAS
COUNTY OF BELL

RANGER TOP LLC, OWNER OF THE 1.003 ACRE TRACT OF LAND SHOWN ON THIS PLAT, AND DESIGNATED HEREIN AS RANGER TOP ADDITION WITHIN THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS, AND WHOSE NAME IS SUBSCRIBED HERETO, HEREBY DEDICATES THE USE OF THE PUBLIC FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS, AND PUBLIC PLACES SHOWN HEREON WITHIN THE PLAT BOUNDARIES OF THIS SUBDIVISION.

RANGER TOP LLC
3413 Hickory View
Harker Heights
Texas, 76548

_____
BY: CHET P. PAUDEL, MANAGING MEMBER

STATE OF TEXAS
COUNTY OF BELL

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED, CHET P. PAUDEL, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME, FOR THE PURPOSES AND CONSIDERATION THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS THE _____ DAY OF_____, 20____.

_____
NOTARY PUBLIC, STATE OF TEXAS

APPROVED THIS _____ DAY OF _____, 2026 BY THE DIRECTOR OF PLANNING AND DEVELOPMENT OF THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS.

_____
DIRECTOR OF PLANNING AND DEVELOPMENT

APPROVED THIS _____ DAY OF _____, 2026 BY THE PLANNING AND ZONING COMMISSION OF THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS.

_____
CHAIRPERSON, PLANNING AND ZONING COMMISSION

_____
SECRETARY, PLANNING AND ZONING COMMISSION

APPROVED THIS _____ DAY OF _____, 2026 BY THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, BELL COUNTY, TEXAS.

_____
MAYOR

_____
CITY SECRETARY

AFFIDAVIT:

The Bell County Tax Appraisal District, the taxing authority for all entities in Bell County, Texas, does hereby certify there are currently no delinquent taxes due or owing on the property described by this plat.

Dated this the _____ day of _____, 20____ A. D.

Bell County Tax Appraisal District

By: _____

STATE OF TEXAS
COUNTY OF BELL

KNOWN ALL MEN BY THESE PRESENTS:

That I, Brett A. Butts, do hereby certify that I prepared this plat from an actual and accurate survey of the land and that the corner monuments shown thereon were properly placed under my personal supervision, in accordance with the Subdivision and Property Development Regulations of the City of Harker Heights, Texas.

Sep 29, 2026
Brett A. Butts, R.P.L.S.

#6254
Registration No.

STATE OF TEXAS · REGISTERED · BRETT A. BUTTS · 6254 · PROFESSIONAL · LAND SURVEYOR

0 30 60 90


■ - Square Concrete Monument Found (Unless otherwise Stated)

RECORDATION INFORMATION:

FILED FOR RECORD THIS _____DAY OF_____, 20____.

IN DOCUMENT NO. _____, OFFICIAL PUBLIC RECORDS OF REAL PROPERTY, BELL COUNTY, TEXAS.


CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C1	31.00'	36.90'	34.76'	S 48°40'13" W	68°11'47"
C2	66.00'	88.20'	81.78'	S 52°51'17" W	76°33'55"
C3	42.00'	56.13'	52.04'	N 52°51'17" E	76°33'55"
C4	40.00'	18.84'	18.66'	N 54°12'42" E	26°58'53"
C5	65.00'	30.24'	29.96'	N 81°01'43" E	26°39'09"



VICINITY MAP
- N.T.S. -

Called 3.817 acres
Hector Ruiz, III, Ryan Enrique Ruiz and Kaitlin Rene Ruiz
Doc. No. 2012-00001602

Matte Bushbaker, Magareta Jutta et al
as per Bell County Tax Appraisal District I.D. #69430



LOT 1
BLOCK 1
GUY'S WITH GREEN SHOES ADDITION
Cab. D, Sl. 312-D

Notes:

1. The bearings cited hereon are based on grid north of the Texas Coordinate System of 1983, Central Zone, as derived from GPS observations. Distances cited hereon are expressed in US Survey Feet as measured horizontally along the surface of the earth. The combined correction factor (CCF) for this project is 0.99985115.
2. Based upon what can be scaled from the graphics shown on Federal Insurance Rate Map (FIRM), Community Panel No. 48027C0225E, dated September 26, 2008, the above shown property does not appear within the "Special Flood Hazard Area", and appears to be situated in Zone X. This flood statement does not imply that this tract will never flood, nor does it create any liability in such event on the part of this surveyor or company.
3. It is intended that a 1' non-access easement shall cover the entire frontage of F.M. 2410 (also known as Knights Way) and the entirety of the Warriors Path Road frontage except for the access point shown hereon.

LOTS - ONE (1)
BLOCKS - ONE (1)
AREA - 1.003 ACRES

OWNER:

RANGER TOP LLC
3413 HICKORY VIEW
HARKER HEIGHTS
TEXAS, 76548

FINAL PLAT of
RANGER TOP ADDITION
a subdivision within the City of Harker Heights, Bell County, Texas.
1.003 Acres, situated in the Elizabeth Dawson Survey, Abstract 258, Bell County, Texas, being all of that certain tract described as 1.0 acre in a General Warranty Deed with Vendor's Lien, to Ranger Top, LLC., recorded in Document No. 2022004499, Official Public Records of Real Property, Bell County, Texas.

Plot Date: 09-29-2026
Survey completed 08-11-2026
Scale: 1" = 30'
Job No. 221372
Dwg No. 221372.3
Drawn by JSM
Surveyor B.A.B. #6254

Copyright 2026 All County Surveying, Inc.

ALL COUNTY SURVEYING, INC.
Tx. Firm No. 10023600
4330 South 5th Street
Temple, Texas 76502
254-778-2272 Killeen 254-634-4636
Fax 254-774-1608
www.allcountysurveying.com

PRELIMINARY CONSTRUCTION PLANS
FOR
HARKER HEIGHTS C STORE AND GAS STATION
HARKER HEIGHTS, TX


LEGEND

- EXIST. CONTOUR
- PROPOSED CONTOUR
- EXISTING FENCE
- EXIST. WATER MAIN
- EXIST. SEWER MAIN
- EXIST. STORM MAIN
- FLOW DIRECTION
- REMOVE AND REPLACE
- PROP. 6" CONCRETE

ABBREVIATION

TC	TOP OF CURB
TP	TOP OF PAVEMENT
FS	FINISH SURFACE
FG	FINISH GRADE
FL	FLOWLINE
HP	HIGH POINT
LP	LOW POINT
TG	TOP OF GRATE
GB	GRADE BREAK
P/L	PROPERTY LINE
R/W	RIGHT OF WAY
SW	SIDEWALK
OHE.	OVERHEAD ELECTRICITY
WM	WATER METER
PP	POWER POLE
TOC	TOP OF CLEANOUT
TSW	TOP OF STEMWALL
FF	FINISHED FLOOR
UE	UTILITY EASEMENT
TRW	TOP OF RETAINING WALL
TF	TOP OF FOOTING
CF	CURB FACE
TCH	TOP OF CHANNEL
BCH	BOTTOM OF CHANNEL
BSL	BUILDING SETBACK LINE
HR	HEIGHT OF RETAINING WALL
RH	RETAINED HEIGHT

PROJECT SITE



VICINITY MAP

NOT TO SCALE

SHEET INDEX

SHEET NO	DESCRIPTION
C.1	COVER SHEET
C.2	SITE PLAN
C.3	GRADING PLAN
C.4	UTILITY PLAN
C.5	PRE-PROJECT DAM
C.6	POST-PROJECT DAM
C.7	UNDERGROUND DETENTION CALCULATIONS

PREPARED BY:
iCIVIL ENGINEERING
1001 W EULESS BLVD, STE 412H
EULESS,TX 76040
TEL.(972) 523-5493
EMAIL:INFO@ICIVILENG.COM
TBPE:F-19293

FEMA ZONE

AS DETERMINED BY THE FLOOD INSURANCE RATE MAPS FOR TARRANT COUNTY, TEXAS, THE SUBJECT PROPERTY DOES NOT LIE WITHIN A SPECIAL FLOOD HAZARD AREA (100 YEAR FLOOD), MAP DATE 09-26-2008 COMMUNITY PANEL NO. 48027C0295E SUBJECT LOT IS LOCATED IN ZONE X.

PROPERTY ADDRESS:
HARKER HEIGHTS C STORE AND GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS,TEXAS 76548

Know what's below. Call before you dig.

iCIVIL ENGINEERING
1001 W EULESS BLVD, STE 412H EULESS, TX 76040
PH: (972) 523-5493
TBPE: F-19293
EMAIL:INFO@ICIVILENG.COM


no.	revision	by	date

scale
horiz
vert
date
MAY 2026

PRELIMINARY PLAN
For Review Only
This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 7/30/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX
COVER SHEET
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548

PROJECT NO.
sheet 1 of 7



iCIVIL ENGINEERING
1001 W EULESS BLVD,
STE 412H EULESS, TX
76040
PH: (972) 523-5493
TBPE: F-19293
EMAIL : INFO@ICIVILENG.COM

no.	revision	by	date

scale	
horiz	
vert	
date	MAY 2026

PRELIMINARY PLAN
For Review Only

This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 7/30/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX

SITEPLAN
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548

PROJECT NO.
sheet 2 of 7

HECTOR RUIZ, III
RYAN ENRIQUE RUIZ and KAITLIN RENE RUIZ
CALLED 3.817 ACRES
(INST. No. 2012-00001602)

WIELAND MANAGEMENT CO., LLC
a Texas Corporation
CALLED 1.204 ACRES
(DOC No. 2016-50845)

WARRIORS PATH ROAD
ROW VARIES

F.M. 2410
ROW VARIES

FF756.00

10' PUBLIC UTILITY EASEMENT

1" NON ACCESS EASEMENT

10' PUBLIC UTILITY EASEMENT

24.0' PIPELINE & ACCESS EASEMENT PER SEPARATE INST.

PROP UNDERGROUND DETENTION PIPE

RELOCATE EXIST 24" CULVERT

PROP 2-24" CULVERT @ 0.5%

24"INV754.18

24"INV754.0

4-6" STEPS

4-4" STEPS

PROP 2.5' RET WALL

PROP 1.0' RET WALL

END RET WALL
TRW752.92
FS752.92
(EP752.92)
RH=0.0'

PROP HANDRAIL

TRW755.90
TF752.40
FS755.40
(EP752.0)
RH=3.4'

TRW755.88
TF749.90
FS755.88
(EG750.4)
RH=5.5'

TRW755.60
TF749.20
FS756.0
TC749.78
RH=5.8'

TC/TP749.28
MATCH EXIST

TC/TP748.64
MATCH EXIST

FS753.69
(EP753.69)

FS753.63
2.4' DEEPEN FOOTING

FS756.00
0' DEEPEN FOOTING

TC755.97
TP755.47

TC755.25
TP754.75

TC755.90
FL755.40
GB

TC757.71
FL757.21
GB

TC757.90
TP757.40

TC757.64
FL757.14

TG755.3

TC757.66
TP757.16

FL756.89

FS755.50

FS757.24

TG755.7

TG755.72
TG755.31

FS756.56

TC755.71
TP755.21

TC755.44
FL754.94

TP755.81

FS755.20

TRW/TF755.12
RH=0.0'

TC755.70
TP755.20
GB

TC756.16
TP755.66
GB

TC755.98
TP755.48

TC755.82
TP755.32

FS752.95

FS756.48

FS756.58

FS756.80

TG755.4

FS756.00

TC759.95
TP759.45

TC759.23
TP758.73

TC760.38
TP759.88

TC759.66
TP759.16

TC762.59
TP762.09

TC761.93
TP761.43

TP761.86
GB

TP758.35

TP760.57

TP758.65

TP759.32

TP759.99

TC761.38
TP760.88
GB

TP756.26

TP756.75

TP757.87

TC758.85
TP758.35

TP756.01

TC756.99
TP756.49
GB

TC768.03
TP767.53

TC766.50
TP766.00

FS765.64

(TC768.11)
(FL767.61)

FS767.19

TP767.00
MATCH EXIST

TP765.44
MATCH EXIST

(TC765.03)
(FL764.53)

S 88°52'32" E 248.05'

N 88°52'39" W 252.72'

N88°51'45"W 135.38'

S88°51'45"E 138.90'

S14°19'46"W 162.89'

S02°54'08"W 60.02'

(EP745.24)

(EP745.38)

(EP745.71)

(EP747.39)


URIAH HUNT SURVEY
ABSTRACT NO. 401

ELIZABETH DAWSON SURVEY
ABSTRACT NO. 258

NORTH


0 20' 40' 60' 80'

SCALE 1"= 20'




DETAIL-A (A)
NOT TO SCALE

NOTE:
(A) TRANSITION FROM 6" CURB TO 0" CURB PER DETAIL A



SECTION B-B
N.T.S.



SECTION A-A
N.T.S.

Harker Heights
The Bright Star Of Central Texas

Texas811
Know what's below. Call before you dig.

iCIVIL ENGINEERING
1001 W EULESS BLVD,
STE 412H EULESS, TX
76040
PH: (972) 523-5493
TBPE: F-19293
EMail: INFO@ICIVILENG.COM

no.	revision	by	date


scale
horiz
vert
date
MAY 2026


PRELIMINARY PLAN
For Review Only

This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 7/30/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX
GRADING PLAN
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548

PROJECT NO.
sheet 3 of 7





UTILITY NOTES:

1. THE CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR HIS MEANS AND METHODS OF CONSTRUCTION, JOB SITE CONDITIONS AND JOB SITE SAFETY, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO WORKING HOURS. THE CONTRACTOR SHALL SAVE, PROTECT, INDEMNIFY, DEFEND AND HOLD HARMLESS THE OWNER, THE ARCHITECT AND THE ENGINEER FROM ANY CLAIM OF LIABILITY, REAL OR ALLEGED, ARISING OUT OF THE PERFORMANCE OF ANY WORK ON THIS PROJECT. THE CONTRACTOR SHALL NAME THE OWNER, THE ARCHITECT AND THE ENGINEER AS "ADDITIONAL INSURED" ON HIS INSURANCE POLICIES.
2. ALL DRY UTILITY INFORMATION SHOWN ON THESE PLANS (GAS, ELECTRIC, CABLE, PHONE, ETC.) IS SHOWN FOR INFORMATION ONLY. THE CONTRACTOR SHALL COORDINATE WITH THE INDIVIDUAL UTILITY COMPANIES FOR FINAL LOCATION OF TRANSFORMERS, SWITCH BOXES, PEDESTALS, AND CONDUIT PRIOR TO INSTALLATION.
3. WHEN WATER AND SEWER LINES ARE INSTALLED IN PROXIMITY TO ONE ANOTHER, SUCH INSTALLATION SHALL BE IN STRICT ACCORDANCE WITH THE RULES AND REGULATIONS OF THE JURISDICTIONAL AUTHORITY. SPECIAL ATTENTION IS CALLED TO REQUIREMENTS FOR BOTH LATERAL AND VERTICAL SEPARATION BETWEEN WATER AND SEWER FACILITIES.
4. THIS PROJECT TO BE BUILT IN ACCORDANCE WITH CITY STANDARDS, SPECIFICATIONS AND DETAILS FOR WATER AND SEWER CONSTRUCTION.
5. THE CONTRACTOR SHALL COMPLY WITH ALL BUILDING CODES AND REGULATIONS, FEDERAL STATE, COUNTY AND CITY SAFETY CODES AND INSPECTION REQUIREMENTS.
6. THE CONTRACTOR SHALL PROVIDE DUST PROTECTION DURING CONSTRUCTION. ALL TRASH AND DEBRIS SHALL BE PICKED UP AT ALL TIMES.
7. WATER LINES SHALL BE PVC IN ACCORDANCE WITH AWAA C-900.
8. WHERE CONSTRUCTION DETAILS AND SPECIFICATIONS ARE NOT NOTED ON THESE PLANS USE CITY OF MANSFIELD STANDARD SPECIFICATIONS FOR DESIGN AND CONSTRUCTION.

NOTE:
CONTRACTOR TO POTHOLE & VERIFY THE LOCATION AND ELEVATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION

NOTE:
EXISTING ABOVE GROUND UTILITIES HAVE BEEN SHOWN BASED ON INFORMATION SHOWN ON A SURVEY OF THE PROPERTY BY OTHERS. UNDERGROUND UTILITIES ARE SHOWN BASED ON RECORD DATA AND MAY NOT BE COMPLETE OR EXACT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS AND DEPTHS OF ALL ABOVE GROUND AND UNDERGROUND UTILITIES AND ESTABLISHING THEIR EXACT LOCATION AND DEPTH PRIOR TO SETTING ANY FINISH GRADE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE TO EXISTING ABOVE GROUND OR UNDERGROUND UTILITIES, INCLUDING THOSE NOT SHOWN ON THE PLANS. THE CONTRACTOR IS ADVISED TO CONTACT THE CITY AND ALL FRANCHISE UTILITY COMPANIES, EASEMENT HOLDERS, ETC. AT LEAST 48 HOURS PRIOR TO BEGINNING EXCAVATION IN THE VICINITY OF ANY UNDERGROUND UTILITY

UNDERGROUND DETENTION SUMMARY

48" ADS N-12 PIPE
TOTAL LENGTH = 150 FT
25 YR WSE = 751.93
STORAGE REQUIRED = 2,570 CF (25YR EVENT)
STORAGE PROVIDED = 3,369 CF
(CHAMBER STORAGE = 1860 CF)
(STONE STORAGE = 1590 CF)
COVER = 2.4 FT (MINIMUM)
BOTTOM OF UG DETENTION = 748.5
TOP OF UG DETENTION = 752.5
TOP OF PAVEMENT = 754.9
FOOTPRINT = 20.58' X 53'
(SEE SHEET 10 FOR CALCULATIONS)

Harker Heights — The Bright Star Of Central Texas

Texas811 — Know what's below. Call before you dig.

iCIVIL ENGINEERING
1001 W EULESS BLVD,
STE 412H EULESS, TX
76040
PH: (972) 523-5493
TBPE: F-19293
EMAIL: INFO@ICIVILENG.COM

no.	revision	by	date

scale
horiz
vert
date
MAY 2026

PRELIMINARY PLAN
For Review Only
This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 7/30/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX
UTILITY PLAN
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548

PROJECT NO.
sheet 4 of 7

PRE-PROJECT RUNOFF CALCULATION

Area ID	Area (acres)	C_2	C_{10}	C_{25}	C_{100}	T_C (min.)	I_2 (in./hr.)	I_{10} (in./hr.)	I_{25} (in./hr.)	I_{100} (in./hr.)	Q_2 (cfs)	Q_{10} (cfs)	Q_{25} (cfs)	Q_{100} (cfs)	COMMENTS
EX-A	1.003	0.43	0.49	0.53	0.59	10.00	4.82	7.14	8.64	11.00	2.08	3.54	4.58	6.54	DRAINS TO EX DITCH ON KNIGHT'S WAY


NOTES:
(1) C VALUE WERE TAKEN FROM CITY OF HARKER HEIGHTS, DRAINAGE CRITERIA MANUAL, TABLE 2-2
(2) INTENSITY VALUES WERE TAKEN FROM NOAA ATLAS 14
(3) MINIMUM TIME OF CONCENTRATION FOR COMMERCIAL DEVELOPMENT = 10 MIN. (FROM CITY OF HARKER HEIGHTS, DRAINAGE CRITERIA MANUAL, PAGE 2-5)
(4) Q=C*I*A

WEIGHTED RUNOFF COEFFICIENT (EX. A)

LAND USE	TOTAL LAND AREA	C2	C10	C25	C100
UNDEVELOPED	0.83	0.37	0.43	0.46	0.53
ASPHALT	0.17	0.73	0.81	0.86	0.90
WEIGHTED RUNOFF COEFFICIENT	1.00	0.43	0.49	0.53	0.59

NOTES:
1. C VALUES WERE TAKEN FROM CITY OF HARKER HEIGHTS, DRAINAGE CRITERIA MANUAL, TABLE 2-2
2. THE WEIGHTED RUNOFF COEFFICIENT IS COMPUTED BY Σ(A*C)/A

NOTE:
ONSITE UNDERGROUND DETENTION SYSTEM PROPOSED TO MANAGE ONSITE DRAINAGE. THE SYSTEM WILL BE FULLY DESIGNED DURING FINAL ENGINEERING DESIGN



NORTH

0 40' 80' 120' 160'

SCALE 1"= 40'

RUNOFF CALCULATION

Q=CIA

WHERE,
C=RUNOFF COEFFICIENT
I=RAINFALL INTENSITY
A=DRAINAGE AREA

LEGEND

DRAINAGE AREA BOUNDARY

FLOW DIRECTION

EX. A / 1.00 AC

ID / AREA (Ac.)

iCIVIL ENGINEERING
1001 W EULESS BLVD,
STE 412H EULESS, TX
76040
PH: (972) 523-5493
TBPE: F-19293
EMAIL: INFO@ICIVILENG.COM

no.	revision	by	date

scale: horiz / vert

date: MAY 2026

PRELIMINARY PLAN
For Review Only

This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 7/30/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX

PRE-PROJECT DAM
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548


PROJECT NO.


sheet 5 of 7

POST-PROJECT RUNOFF CALCULATION

Area ID	Area (acres)	C_2	C_{10}	C_{25}	C_{100}	T_C (min.)	I_2 (in./hr.)	I_{10} (in./hr.)	I_{25} (in./hr.)	I_{100} (in./hr.)	Q_2 (cfs)	Q_{10} (cfs)	Q_{25} (cfs)	Q_{100} (cfs)	COMMENTS
A	0.166	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	0.60	0.98	1.26	1.77	DRAINS TO NE SIDE OF PROPERTY
B	0.010	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	0.04	0.06	0.08	0.11	DRAINS TO GRATE INLET 1
C	0.015	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	0.05	0.09	0.11	0.16	DRAINS TO GRATE INLET 2 & 3
D	0.098	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	0.35	0.58	0.75	1.05	DRAINS TO GRATE INLET 1, 2 & 3
E	0.509	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	1.84	3.02	3.87	5.43	DRAINS TO GRATE INLET 4
F	0.187	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	0.68	1.11	1.42	2.00	DRAINS TO EX DITCH ON KNIGNT'S WAY
G	0.018	0.75	0.83	0.88	0.97	10.00	4.82	7.14	8.64	11.00	0.07	0.11	0.14	0.19	DRAINS TO GRATE INLET 5

NOTES:
(1) C VALUE WERE TAKEN FROM CITY OF HARKER HEIGHTS, DRAINAGE CRITERIA MANUAL, TABLE 2-2
(2) INTENSITY VALUES WERE TAKEN FROM NOAA ATLAS 14
(3) MINIMUM TIME OF CONCENTRATION FOR COMMERCIAL DEVELOPMENT = 10 MIN. (FROM CITY OF HARKER HEIGHTS, DRAINAGE CRITERIA MANUAL, PAGE 2-5)
(4) Q=C*I*A





RUNOFF CALCULATION

Q=CIA

WHERE,
C=RUNOFF COEFFICIENT
I=RAINFALL INTENSITY
A=DRAINAGE AREA

LEGEND

DRAINAGE AREA BOUNDARY

FLOW DIRECTION

A
0.166 AC

ID
AREA (Ac)

iCIVIL ENGINEERING
1001 W EULESS BLVD,
STE 412H EULESS, TX
76040
PH: (972) 523-5493
TBPE: F-19293
EMAIL: INFO@ICIVILENG.COM


no.	revision	by	date

scale
horiz
vert
date
MAY 2026

PRELIMINARY PLAN
For Review Only
This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 7/30/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX
POST-PROJECT DAM
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548

PROJECT NO.
sheet 6 of 7



Routing Diagram for DET ANALYSIS
Prepared by ICivil Engineering, Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC

DET ANALYSIS *Belton TX PF_Intensity_English_PDS 2-yr Duration=10 min, Inten=4.82 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 1

Summary for Pond 5P: Storage

Inflow Area = 0.650 ac, 0.00% Impervious, Inflow Depth = 0.71" for 2-yr event
Inflow = 2.73 cfs @ 0.17 hrs, Volume= 0.038 af
Outflow = 0.44 cfs @ 0.31 hrs, Volume= 0.033 af, Atten= 84%, Lag= 8.4 min
Primary = 0.44 cfs @ 0.31 hrs, Volume= 0.033 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
Peak Elev= 750.35' @ 0.31 hrs Surf.Area= 0.025 ac Storage= 0.032 af

Plug-Flow detention time= 30.8 min calculated for 0.033 af (86% of inflow)
Center-of-Mass det. time= 30.1 min (40.1 - 10.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	748.00'	0.035 af	**20.58'W x 53.00'L x 5.50'H Field A** 0.138 af Overall - 0.051 af Embedded = 0.087 af x 40.0% Voids
#2A	748.50'	0.043 af	**ADS N-12 48"** x 9 Inside #1 Inside= 47.7"W x 47.7"H => 12.40 sf x 20.00'L = 248.0 cf Outside= 54.0"W x 54.0"H => 14.85 sf x 20.00'L = 297.0 cf Row Length Adjustment= -10.00' x 12.40 sf x 3 rows
		0.077 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	748.50'	**5.0" Round Culvert** L= 100.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 748.50' / 748.00' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.14 sf

Primary OutFlow Max=0.44 cfs @ 0.31 hrs HW=750.35' (Free Discharge)
1=Culvert (Barrel Controls 0.44 cfs @ 3.23 fps)

DET ANALYSIS *Belton TX PF_Intensity_English_PDS 2-yr Duration=10 min, Inten=4.82 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 2

Pond 5P: Storage



DET ANALYSIS *Belton TX PF_Intensity_English_PDS 10-yr Duration=10 min, Inten=7.14 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 3

Summary for Pond 5P: Storage

Inflow Area = 0.650 ac, 0.00% Impervious, Inflow Depth = 1.05" for 10-yr event
Inflow = 4.05 cfs @ 0.17 hrs, Volume= 0.057 af
Outflow = 0.54 cfs @ 0.31 hrs, Volume= 0.051 af, Atten= 87%, Lag= 8.7 min
Primary = 0.54 cfs @ 0.31 hrs, Volume= 0.051 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
Peak Elev= 751.28' @ 0.31 hrs Surf.Area= 0.025 ac Storage= 0.048 af

Plug-Flow detention time= 39.5 min calculated for 0.051 af (91% of inflow)
Center-of-Mass det. time= 38.7 min (48.8 - 10.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	748.00'	0.035 af	**20.58'W x 53.00'L x 5.50'H Field A** 0.138 af Overall - 0.051 af Embedded = 0.087 af x 40.0% Voids
#2A	748.50'	0.043 af	**ADS N-12 48"** x 9 Inside #1 Inside= 47.7"W x 47.7"H => 12.40 sf x 20.00'L = 248.0 cf Outside= 54.0"W x 54.0"H => 14.85 sf x 20.00'L = 297.0 cf Row Length Adjustment= -10.00' x 12.40 sf x 3 rows
		0.077 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	748.50'	**5.0" Round Culvert** L= 100.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 748.50' / 748.00' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.14 sf

Primary OutFlow Max=0.54 cfs @ 0.31 hrs HW=751.28' (Free Discharge)
1=Culvert (Barrel Controls 0.54 cfs @ 3.92 fps)

DET ANALYSIS *Belton TX PF_Intensity_English_PDS 10-yr Duration=10 min, Inten=7.14 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 4

Pond 5P: Storage



DET ANALYSIS *Belton TX PF_Intensity_English_PDS 25-yr Duration=10 min, Inten=8.64 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 5

Summary for Pond 5P: Storage

Inflow Area = 0.650 ac, 0.00% Impervious, Inflow Depth = 1.27" for 25-yr event
Inflow = 4.90 cfs @ 0.17 hrs, Volume= 0.069 af
Outflow = 0.59 cfs @ 0.31 hrs, Volume= 0.063 af, Atten= 88%, Lag= 8.8 min
Primary = 0.59 cfs @ 0.31 hrs, Volume= 0.063 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
Peak Elev= 751.93' @ 0.31 hrs Surf.Area= 0.025 ac Storage= 0.059 af

Plug-Flow detention time= 44.0 min calculated for 0.063 af (92% of inflow)
Center-of-Mass det. time= 43.7 min (53.7 - 10.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	748.00'	0.035 af	**20.58'W x 53.00'L x 5.50'H Field A** 0.138 af Overall - 0.051 af Embedded = 0.087 af x 40.0% Voids
#2A	748.50'	0.043 af	**ADS N-12 48"** x 9 Inside #1 Inside= 47.7"W x 47.7"H => 12.40 sf x 20.00'L = 248.0 cf Outside= 54.0"W x 54.0"H => 14.85 sf x 20.00'L = 297.0 cf Row Length Adjustment= -10.00' x 12.40 sf x 3 rows
		0.077 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	748.50'	**5.0" Round Culvert** L= 100.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 748.50' / 748.00' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.14 sf

Primary OutFlow Max=0.59 cfs @ 0.31 hrs HW=751.92' (Free Discharge)
1=Culvert (Barrel Controls 0.59 cfs @ 4.34 fps)

DET ANALYSIS *Belton TX PF_Intensity_English_PDS 25-yr Duration=10 min, Inten=8.64 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 6

Pond 5P: Storage



DET ANALYSIS *Belton TX PF_Intensity_English_PDS 100-yr Duration=10 min, Inten=11.04 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 7

Summary for Pond 5P: Storage

Inflow Area = 0.650 ac, 0.00% Impervious, Inflow Depth = 1.62" for 100-yr event
Inflow = 6.26 cfs @ 0.17 hrs, Volume= 0.088 af
Outflow = 0.71 cfs @ 0.31 hrs, Volume= 0.082 af, Atten= 89%, Lag= 8.8 min
Primary = 0.71 cfs @ 0.31 hrs, Volume= 0.082 af

Routing by Stor-Ind method, Time Span= 0.00-3.00 hrs, dt= 0.01 hrs
Peak Elev= 753.41' @ 0.31 hrs Surf.Area= 0.025 ac Storage= 0.076 af

Plug-Flow detention time= 50.5 min calculated for 0.082 af (93% of inflow)
Center-of-Mass det. time= 50.3 min (60.3 - 10.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	748.00'	0.035 af	**20.58'W x 53.00'L x 5.50'H Field A** 0.138 af Overall - 0.051 af Embedded = 0.087 af x 40.0% Voids
#2A	748.50'	0.043 af	**ADS N-12 48"** x 9 Inside #1 Inside= 47.7"W x 47.7"H => 12.40 sf x 20.00'L = 248.0 cf Outside= 54.0"W x 54.0"H => 14.85 sf x 20.00'L = 297.0 cf Row Length Adjustment= -10.00' x 12.40 sf x 3 rows
		0.077 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	748.50'	**5.0" Round Culvert** L= 100.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 748.50' / 748.00' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.14 sf

Primary OutFlow Max=0.71 cfs @ 0.31 hrs HW=753.41' (Free Discharge)
1=Culvert (Barrel Controls 0.71 cfs @ 5.18 fps)

DET ANALYSIS *Belton TX PF_Intensity_English_PDS 100-yr Duration=10 min, Inten=11.04 in/hr*
Prepared by ICivil Engineering Printed 5/19/2026
HydroCAD® 10.20-8a s/n 14126 © 2025 HydroCAD Software Solutions LLC Page 8

Pond 5P: Storage



UNDERGROUND DETENTION SUMMARY

AREA	PEAK RUNOFF INFLOW(cfs)				PEAK RUNOFF OUTFLOW(cfs)				REMARKS
	2 YEAR	10 YEAR	25 YEAR	100 YEAR	2 YEAR	10 YEAR	25 YEAR	100 YEAR	
B+C+D+E+G	2.73	4.05	4.90	6.26	0.49	0.58	0.63	0.74	REFER TO POST PROJECT DAM FOR AREA AND PEAK RUNOFF INFLOW DATA. REFER TO UNDERGROUND DETENTION CALCULATION SHEET (SHT 11A & 11B) FOR PEAK RUNOFF OUTFLOW DATA

ONSITE RUNOFF SUMMARY

PRE PROJECT RUNOFF (cfs)				POST PROJECT RUNOFF(cfs)				▲ (POST-PRE)				REMARKS
2 YEAR	10 YEAR	25 YEAR	100 YEAR	2 YEAR	10 YEAR	25 YEAR	100 YEAR	2 YEAR	10 YEAR	25 YEAR	100 YEAR	
2.08	3.54	4.58	6.54	1.77	2.67	3.31	4.73	-0.32	-0.87	-1.26	-1.81	REFER TO PRE PROJECT DAM(SHT 8) FOR PRE PROJECT RUNOFF DATA. REFER TO UNDERGROUND DETENTION CALCULATION SHEET(SHT 11A & 11B) & POST PROJECT DAM (SHT 10) SHEET POST PROJECT RUNOFF DATA.

NOTE:
1) POST PROJECT RUNOFF FOR GIVEN STORM FREQUENCY = DETENTION POND OUTFLOW FOR GIVEN YEAR + DRAINAGE AREA (A+F)

Harker Heights — The Bright Star Of Central Texas

Texas811 — Know what's below. Call before you dig.

iCIVIL ENGINEERING
1001 W EULESS BLVD,
STE 412H EULESS, TX 76040
PH: (972) 523-5493
TBPE: F-19293
EMAIL:INFO@ICIVILENG.COM

no.	revision	by	date

scale
horiz
vert
date
MAY 2026

PRELIMINARY PLAN
For Review Only
This document is released for the purpose of interim review and markup under the authority of OM GHARTY CHHETRI, P.E. Licence No: 106562 on 5/21/26. This document is not to be used for construction, bidding or permit purposes.

CITY OF HARKER HEIGHTS, TX
UNDERGROUND DETENTION CALCULATION
FOR
HARKER HEIGHTS C STORE & GAS STATION
1829 FARMS TO MARKET 2410
HARKER HEIGHTS, TX 76548

PROJECT NO.
sheet 7 of 7

RANGER TOP ADDITION

P26-13 – Ranger Top Final Plat

Plat Distributed to HH Staff & Public Utilities: 9/30/2026
Sent to Applicant 10/14/2026

No Response To Date – Comments may be forthcoming
Oncor
Atmos
Brightspeed
KISD
Fire Department
Building Official

Bell County Public Health – No comments

TXDOT – TxDOT will need additional information before approval can be considered. Please complete the attached Minor Traffic Study (see attached) so that TxDOT can determine whether a Traffic Impact Analysis (TIA) will be required for the proposed development.

Planning & Development

1. No comments

Public Works

1. Per §154.21(C)(2)(d), the applicant shall provide a sidewalk layout along the northern right-of-way (ROW) of FM 2410/Knights Way. The proposed sidewalk shall be designed in accordance with the City's Mobility 2030 Plan, which specifies a sidewalk width of 6 to 10 feet for this area
2. The Agreement for Sanitary Sewer Easement and Future Plat Dedication (Separate Instrument) identifies the parties' properties as 1827 E. FM 2410 (Tract A) and 1329 E. FM 2410 (Tract B). However, the property records and submitted application materials identify Tract B as 1829 E. FM 2410. Revise and resubmit the easement agreement to reflect the correct property address and ensure that all applicable grantor and grantee information is accurate and consistent with the property records and submitted documents.
3. The Municipal Public Sanitary Sewer System does not begin, traverse, or terminate within either subject property: 1827 E. FM 2410/Knights Way (Tract A) or 1829 E. FM

2410/Knights Way (Tract B). The municipal public sanitary sewer system connection begins at the sanitary sewer manhole located at the northwestern corner of 1825 E. FM 2410/Knights Way, within the 10-foot Public Utility Easement.

a. The Agreement for Sanitary Sewer Easement and Future Plat Dedication shall be revised to clearly establish access rights through the entirety of the property or properties containing the sanitary sewer infrastructure, including provisions for routine and emergency inspection, maintenance, repair, and replacement. The agreement shall ensure that the grantor(s) and grantee(s), as applicable, have sufficient legal access to the portions of adjacent properties through which the sanitary sewer easement and associated infrastructure extend, without being unreasonably denied or prevented from accessing the facilities.
b. The sanitary sewer infrastructure serving 1827 E. FM 2410/Knights Way currently traverses 1825 E. FM 2410/Knights Way before connecting to the municipal public sanitary sewer system. Accordingly, the necessary easement and access rights must be established to allow the owner(s) of 1827 to access and maintain the sewer infrastructure located on 1825.

   Additionally, a separate agreement between the owners of 1829 and 1825 E. FM 2410/Knights Way, or an appropriately structured agreement among all affected property owners, shall be provided to ensure that the owner(s) of 1829 retain the legal right to access, inspect, maintain, repair, and replace the sanitary sewer infrastructure serving their property, including any portions located on 1825, without being dependent solely on the consent or actions of the owner(s) of 1827.

   This requirement is particularly important because the submitted plans indicate that the sanitary sewer service for 1829 is proposed to connect to the sewer line serving 1827 rather than connect independently to the municipal public sanitary sewer system. All necessary easements, access rights, and maintenance provisions shall be documented to ensure continued access to the sewer infrastructure by all affected property owners and to address routine and emergency maintenance needs.

4. The proposed private sanitary sewer easement is shown at a width of 10 feet. Pursuant to §154.42(A)(1), all water and sanitary sewer utility easements shall have a minimum width of 15 feet. Revise the plat and proposed easement documentation to provide a minimum 15-foot-wide sanitary sewer easement.
5. The existing Public Utility Easements (PUEs) along the frontages of FM 2410/Knights Way and Warriors Path are not identified on the submitted plat. Revise the plat to identify

and delineate all existing and proposed public and private utility easements, including their locations and widths.

6. Pursuant to §154.21(C)(1)(g) and (j) and §154.42(C), provide the required off-site easement documentation for the proposed 24-foot Fire Lane and Access Easement. The easements shall be properly executed, notarized, and recorded. Provide evidence of recordation to the City.

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

DISCUSSION AND POSSIBLE ACTION REGARDING APPROVAL OF A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, TEXAS, AUTHORIZING THE SUBMISSION OF AN APPLICATION FOR THE 2027-2028 TXCDBG COMMUNITY DEVELOPMENT FUND COMPETITION. (RESOLUTION #2026-36; PROJECT MANAGER)

EXPLANATION:

The 2027-2028 Texas Community Development Block Grant Program's (TxCDBG) Community Development Fund Community Application, through the Texas Department of Agriculture, facilitates state-administered federal block grant funding to build viable communities, improve basic infrastructure, and support low- and moderate-income (LMI) residents.

The Community Application receives maximum scores for First Tier Priorities, set by the Central Texas Council of Governments (CTCG). First Tier activities for the City's region include:

- Flood drainage improvements (03I)
- Water/sewer improvements (03J)
- Street improvements (03K)
- Sidewalks (03L)
- Fire station/equipment (03O)
- Single-unit residential rehab, utility connections (14A)

The City of Harker Heights is submitting a TxCDBG grant application for the 2026-2027 Street Improvements Project; W. Valley Road, Phase 1, with the requested commitments:

- TxCDBG: $750,000.00
- City of Harker Heights: $112,500.00 - (15% of total cost; population based)
- Total Financial Commitment: $862,500.00

The Engineer's Opinion of Probable Construction Cost (OPCC) is $850,000.00

The TxCDBG application is due by November 19, 2026.

RECOMMENDATION:

Staff recommends approval of Resolution #2026-36 authorizing submission of a TxCDBG Community Development Bock Grant Program Application to the Texas Department of Agriculture

ACTION BY THE CITY COUNCIL:

1. Motion to **approve / disapprove** Resolution #2026-36.
2. Any other action desired

ATTACHMENTS:

W. Valley Road Improvements PH 1 - OPCC
W. Valley Road Improvments PH 1 - Exhibit
Resolution 2026-36 - WORD

PRELIMINARY OPINION OF PROBABLE CONSTRUCTION COSTS

KASBERG, PATRICK & ASSOCIATES, LP
CONSULTING ENGINEERS
Temple, Texas

Client: City of Harker Heights
Project: W. Valley Road - Lynn Dr. to Randy Blvd. (875 LF)
36-Foot BOC-BOC Section

Date: October 22, 2026
By: JAS

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT AMOUNT	EXTENDED AMOUNT
A. STREET IMPROVEMENTS					
1	Mobilization, Bonds & Insurance, not-to-exceed 5% of the Base Bid Amount	LS	100%	$ 27,100.00	$ 27,100.00
2	Implement Traffic Control Plan	LS	100%	10,000.00	10,000.00
3	Implement & Administer Stormwater Pollution Prevention Plan, Including Submission to & Receiving Permits from TCEQ	LS	100%	6,500.00	6,500.00
4	DVD of ROW Pre-Construction & Post Construction Site Conditions for Total Project	LS	100%	1,250.00	1,250.00
5	Sawcut Existing Asphalt	LF	125	8.00	1,000.00
6	Roadway Excavation (12-Inch Depth)	SY	3,700	30.00	111,000.00
7	Proofroll Subgrade	SY	3,700	1.00	3,700.00
8	Geogrid	SY	3,700	5.00	18,500.00
9	Crushed Limestone Base (TxDOT Type A, Gr 1-2)(6" Depth)	SY	3,700	14.00	51,800.00
10	Crushed Limestone Base (TxDOT Type A, Gr 1-2)(4" Depth)	SY	3,200	12.00	38,400.00
11	Furnish & Place 2" Type 'D' HMAC Pavement with Prime & Tack Coat	TN	400	290.00	116,000.00
12	Curb and Gutter	LF	1,360	25.00	34,000.00
13	Concrete Driveway Replacement	SY	390	165.00	64,350.00
14	Blue Reflective Fire Hydrant Buttons	EA	1	15.00	15.00
15	6" Topsoil (3-Foot Behind Curb)	SY	600	4.50	2,700.00
16	Revegetation (3-Feet Behind Curb)	SY	600	11.00	6,600.00
17	Utility Adjustment Allowance	LS	100%	75,000.00	75,000.00
				SUBTOTAL A. STREET IMPROVEMENTS	$ 567,915.00
				CONTINGENCY (20%)	$ 113,583.00
				ENGINEERING SERVICES (DESIGN, BIDDING, CONSTRUCTION ADMINISTRATION)	$ 102,300.00
				GEOTECHNICAL ENGINEERING	$ 9,500.00
				LIDAR DRONE SURVEYING	$ 8,500.00
				ONSITE REPRESENTATION	$ 45,000.00
				PROJECT TOTAL	$ 846,798.00
				PROJECT TOTAL TO USE	**$ 850,000.00**

Notes:
1. Preliminary OPC does not include costs for construction testing.
2. OPC assumes no storm sewer or drainage improvements will be required.
3. An allowance is provided for minor utility adjustments.
4. OPC assumes no ROW or easements acquisitions will be required.
5. Onsite representation is based on 4-hours per day average coverage.

10/22/2026

STATE OF TEXAS
JOHN A. SIMCIK
92639
LICENSED
PROFESSIONAL ENGINEER

CITY OF HARKER HEIGHTS, TEXAS

W. VALLEY RD IMPROVEMENTS

KASBERG, PATRICK & ASSOCIATES, LP
COUNTY ROAD 4959
TEMPLE, TEXAS 76501
Firm Registration No. F-510

OCTOBER 2026

EXHIBIT A

This document is released for the purpose of interim review under the authority of John A. Simon, P.E. 92539 on 10/20/2026. It is not to be used for construction, bidding or permit purposes.

P:\Harker Heights\2026\20XX-XXX W. Valley Rd Improvements\CAD\02_Exhibits\XXXX-XXX W. Valley Rd Improvements_Exhibit.dwg - 11x17 L KPA-Exh

RESOLUTION NO. 2026-36

A RESOLUTION OF THE CITY OF HARKER HEIGHTS, TEXAS AUTHORIZING THE SUBMISSION OF A TEXAS COMMUNITY DEVELOPMENT BLOCK GRANT PROGRAM APPLICATION TO THE TESAS DEPARTMENT OF AGRICULTURE FOR THE COMMUNITY DEVELOPMENT FUND.

WHEREAS, The City Council of the City of Harker Heights desires to develop a viable community, including decent housing and suitable living environment and expanding economic opportunities, principally for persons of low-to-moderate income; and

WHEREAS, it is necessary and in the best interest of the City of Harker Heights to apply for funding under the Texas Community Development Block Grant Program;

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, **TEXAS** that a Texas Community Development Block Grant Program application for the Community Development Fund is hereby authorized to be filed on behalf of the City with the Texas Department of Agriculture, and to be placed in competition for funding under the Community Development Fund.

FURTHER RESOLVED that the City of Harker Heights commits to dedicating no less than 51% of grant funds for activities identified by the state planning region as First Priority

FURTHER RESOLVED that all funds will be used in accordance with all applicable federal, state, local, and programmatic requirements including but not limited to procurement, environmental review, labor standards, real property acquisition, and civil rights requirements.

FURTHER RESOLVED that the City of Harker Heights is committing to provide $112,500.00 in matching funds toward the application's activities, with the specific usage and funding source to be determined prior to any award of grant funding

PASSED AND APPROVED AT A REGULAR MEETING OF THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, TEXAS, THIS 3rd DAY OF NOVEMBER 2026, AT WHICH MEETING A QUORUM WAS PRESENT, HELD IN ACCORDANCE WITH THE PROVISIONS OF THE TEXAS GOVERNMENT CODE, CHAPTER 551.

CITY OF HARKER HEIGHTS, TEXAS:

_____
Michael D. Blomquist
Mayor

ATTEST:

_____
Julie Helsham, City Secretary

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

DISCUSSION AND POSSIBLE ACTION REGARDING APPROVAL OF A SIGNATORY RESOLUTION AUTHORIZING SIGNATORIES FOR THE 2027-2028 APPLICATION AND FUTURE GRANTS ADMINISTERED THROUGH TEXAS DEPARTMENT OF AGRICULTURE TDA-GO GRANTS ONLINE PORTAL. (RESOLUTION #2026-37; PROJECT MANAGER)

EXPLANATION:

The 2027-2028 Texas Community Development Block Grant Program's (TxCDBG) Community Development Fund Community Application, through the Texas Department of Agriculture, facilitates state-administered federal block grant funding to build viable communities, improve basic infrastructure, and support low- and moderate-income (LMI) residents.

The City of Harker Heights is submitting a TxCDBG grant application for the 2026-2027 Street Improvements Project; W. Valley Road, Phase 1

The Signatory Resolution is required by the Texas Department of Agriculture to allow City Staff to submit, review, process, and execute contractual documents and payment request forms through the TDA-GO Management System.

The TxCDBG application is due by November 19, 2026.

RECOMMENDATION:

Staff recommends approval of Resolution #2026-37 authorizing City Representatives in matters pertaining to the City's participation in the TxCDBG

ACTION BY THE CITY COUNCIL:

1. Motion to **approve / disapprove** Resolution #2026-37.
2. Any other action desired.

ATTACHMENTS:

Resolution 2026-37

RESOLUTION NO. 2026-37

A RESOLUTION OF THE CITY OF HARKER HEIGHTS, TEXAS AUTHORIZING CITY REPRESENTATIVES IN MATTERS PERTAINING TO THE CITY'S PARTICIPATION IN THE TEXAS COMMUNITY DEVELOPMENT BLOCK GRANT PROGRAM.

WHEREAS, The City Council of the City of Harker Heights desires to develop a viable community, including decent housing and suitable living environment and expanding economic opportunities, principally for persons of low-to-moderate income; and

WHEREAS, it is necessary and in the best interest of the City of Harker Heights to participate in the Texas Community Development Block Grant Program; and

WHEREAS, the City Council of the City of Harker Heights is committed to compliance with federal, state, and program rules, including the current TxCDBG Project Implementation Manual;

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, **TEXAS** that the City Council directs and designates the following to act in all matters in connection with any grant application and the County's participation in the Texas Community Development Block Grant Program:

The **City Manager** shall services as the City's Chief Executive Officer and Authorized representative to:

- Execute a grant application and any subsequent contractual documents; and
- Certify environmental review documents between the Texas Department of Agriculture and the City/County; and
- Certify the Payment Request form and/or other forms required for requesting funds to reimburse project costs; and
- Be assigned the role of Authorized Official in the TDA-GO grant management system.

In addition to the above designated officials, should any grant be funded the **City Finance Director** is authorized to:

- Certify the Payment Request form and/or other forms required for requesting funds to reimburse project costs; and
- Prepare and submit other financial documentation; and
- Be assigned the role of Project Director or Payment Processor in the TDA-GO grant management system

PASSED AND APPROVED AT A REGULAR MEETING OF THE CITY COUNCIL OF THE CITY OF HARKER HEIGHTS, TEXAS, THIS 3rd DAY OF NOVEMBER 2026, AT WHICH MEETING A QUORUM WAS PRESENT, HELD IN ACCORDANCE WITH THE PROVISIONS OF THE TEXAS GOVERNMENT CODE, CHAPTER 551.

CITY OF HARKER HEIGHTS, TEXAS:

_____
Michael D. Blomquist
Mayor

ATTEST:

_____
Julie Helsham, City Secretary

City Council Memorandum

FROM: The Office of the City Manager **DATE: November 03, 2026**

RECEIVE AND DISCUSS A PRESENTATION REGARDING THE CITY'S SOLID WASTE COLLECTION AND DISPOSAL SERVICES. (CITY MANAGER)

EXPLANATION:

The City of Harker Heights and Waste Management of Texas, Inc. have been exploring several options for the continued collection, transportation, and disposal of residential and commercial garbage and trash within the City. This presentation will provide an overview of the options for council input and consideration.

ACTION BY THE CITY COUNCIL:

None.